

P. O. BOX 1810 - 1810 E. HAZELTON AVENUE
STOCKTON, CALIFORNIA 95201
(209) 468-3000 FAX (209) 468-2999
www.sjgov.org/pubworks

Modification or Addition to San Joaquin County Improvement Standards


Modification Number: **2015-1**

Effective Date of Change: 5-27-15

Description of Modification:

1. **Standard Drawing R-1:** The sidewalk width dimension on RESIDENTIAL and RURAL RESIDENTIAL street sections has been revised from 4'-6" to 5'-0" to match R-6.
2. **Standard Drawing R-7:** The overall vertical curb depth dimension has been revised from 1'-2" to 1'-1/2". (fixed drafting error)
3. **Standard Drawing R-10B:** The Detectable Warning Surface depiction has been modified to coincide with Note 10 which states it shall be between 6" and 8" from the gutter flowline. The base of the gutter depiction has been modified to be level. (drafting revision)
4. **Standard Drawing R-10C:** The Detectable Warning Surface depiction as shown on the Curb Ramp Lip Detail has been modified to coincide with Standard Drawing R-10B Note 10 which states it shall be between 6" and 8" from the gutter flowline. (drafting revision)
5. **Standard Drawing R-11:** Modified to depict a continuous curb (depressed) through the curb ramp. (drafting revision)
6. **Standard Drawing R-13 & R-14:** The overall depth dimension as shown in detail Section A-A has been revised from 6" to 8". (Fixed typo)
7. **Standard Drawing R-24:** Modified to depict a continuous curb (depressed) through the curb ramp. (drafting revision)
8. **Standard Drawing R-28B:** The overall width dimension of the monument frame, cover assembly, and concrete collar, has been revised from 12" to ID Cover Frame + 1'-0". The concrete collar width dimension has been revised from 3" to 6". The PVC pipe diameter dimension has been revised from 6" OD to 6" ID.
9. **Section 2-5 Trench Cut Policy:** Revised references within the Trench Cutting Policy section of the Improvement Standards from the Department Administration Manual to the Improvement Standards. Also updated references to drawing numbers.
10. **Standard Drawing R-36 & R-37:** Revised references within the two drawings from the Department Administration Manual to the Improvement Standards.


Modification reviewed by:



Fritz Buchman, Deputy Director, Development Services

5/12/15
Date

Modification approved by:



Mike Selling, Deputy Director

5/20/15
Date