

CORNER RECORD

Document Number CR-17-189

City of Lodi

County of San Joaquin, California

Brief Legal Description Center of the intersection of Harney Lane and S. Hutchins St.

	CORNER TYPE	COORDINATES(Optional)
<u>14</u>	<u>13</u>	N. _____
<u>23</u>	<u>24</u>	E. _____
	Government Corner <input type="checkbox"/>	Control <input type="checkbox"/>
	Meander <input type="checkbox"/>	Property <input type="checkbox"/>
	Rancho <input type="checkbox"/>	Other <input checked="" type="checkbox"/>
	Date of Survey <u>April 4, 2016</u>	Zone _____ NAD27 <input type="checkbox"/> NAD83 <input type="checkbox"/>
		NAD83 Epoch _____
		Elev. _____
		Vert. Datum: NGVD29 <input type="checkbox"/> NADV88 <input type="checkbox"/>
		Meas. Units: Metric <input type="checkbox"/> Imperial <input checked="" type="checkbox"/>

T3N, R6E, MDM

Corner - Left as found Found and tagged Established Reestablished Rebuilt

Identification and type of corner found: Evidence used to identify or procedure used to establish or reestablish the corner:

The purpose of this corner record is to establish the position of a found monument in relation to set reference points so that we can reestablish the monument at the conclusion of the Harney lane grade separation project.
No attempt was made to determine the validity of said monument or it's proper location in relation to legal boundary lines in the area.

A description of the physical condition of the monument as found and as set or reset: Found monument was a 3/4" rebar no tag in a monument well with no lid.

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with

the Land Surveyor's Act on JUNE 6, 2017.

Signed [Signature] (P.L.S.) or R.C.E. No.: 7803



COUNTY SURVEYOR'S STATEMENT

This Corner Record was received June 21, 2017 and examined

and filed July 13, 2017

Signed [Signature] P.L.S. or R.C.E. No.: 4842

Title County Surveyor

County Surveyor's Comment _____





S. HUTCHINS STREET

SCRIBED "X" ON CONCRETE

SCRIBED "X" ON CONCRETE

HARNEY LANE

3/4" REBAR NO TAG
IN MONUMENT WELL
PER M&P 22-36

SCRIBED "X" ON CONCRETE

SET COTTON SPINDLE

WEST LANE

LEGEND

- ✱ FOUND MONUMENT AS NOTED
- △ SET REFERENCE POINTS AS SHOWN

N 40° 05' 58" W
81.60'

N 36° 13' 16" E
72.27'

S 30° 45' 29" W
154.53'

S 51° 09' 41" W
80.93'