

By Deputy: aambriz



NOTICE OF EXEMPTION

TO: Office of Planning and Research
CEQAnet Web Portal
<https://ceqasubmit opr.ca.gov/>

FROM: San Joaquin County
Department of Public Works
1810 East Hazelton Avenue
Stockton, California 95205

County Clerk
County of San Joaquin California
44 North San Joaquin Street, Suite 260
Stockton, California 95202

Project Title: Groves Road and San Julian Road Resurfacing

Project Location: See attached vicinity map

Description of Nature, Purpose, and Beneficiaries: See attached project description

Public Agency Approving Project: San Joaquin County Public Works Department

Name of Agency Carrying Out Project: San Joaquin County Public Works Department

This is to advise that the San Joaquin County Public Works Department has approved the above described project on 11/26/2025 and has made the determination that the project is exempt due to the following:

Exempt Status (check one):

- Ministerial (Sec. 21080 (b) (1); 15268)
 Declared Emergency (Sec. 21080 (b) (3); 15269(a))
 Emergency Project (Sec. 21080 (B) (4); 15269(b) (c))
 Categorical Exemption: Existing Facilities (Sec. 15301 (c))
 Statutory Exemption (Sec. 15282(l))

Reason(s) why project is exempt: The project will repair existing roads and will not result in any major alterations to the configuration of the roads. No additional vehicle travel lanes will be constructed.

Lead Agency Contact Person: Fatima Gutierrez, Assistant Planner, (209) 468-3035

Signature: Fatima Gutierrez Title: Assistant Planner Date: 1/21/2026

GROVES ROAD AND SAN JULIAN ROAD RESURFACING

Project Description

Project Location:

Groves Road: Escalon-Bellota Road to east end; **San Julian Road:** west end to Escalon-Bellota Road. See attached Vicinity Map.

Project Justification:

Groves Road formally known as Hartley Road has an unknown original construction date and structural section. The road is 18 feet wide and has been periodically chip sealed by Road Maintenance with the most recent occurring in 2024. San Julian Road formally known as Edinger Road has an unknown original construction date and structural section. The road is 16 feet wide and has been periodically chip sealed by Road Maintenance with the most recent occurring in 2024.

Groves Road exhibits a high amount of longitudinal and edge cracking; a medium amount of block cracking; and a low amount of alligator cracking and rutting. San Julian Road exhibits a high amount of longitudinal and edge cracking; a medium amount of block cracking and alligator cracking; and a low amount rutting.

Scope of Work:

The project will consist of:

1. Resurfacing existing roadway with 0.17 feet of Hot Mix Asphalt (HMA) (Type A).
2. Repairing pavement structural failure areas with full depth 0.50 feet HMA (Type A).
3. Applying Penetration Treatment at all intersection radii plus 50 feet or to conform.
4. Adjusting Existing frame(s) and cover(s) of monuments and utilities to finished grade.
5. Replenishing shoulder backing varying between 4 to 6 feet as called out by Engineer.
6. Paving Driveways (Type D and E).


Environmental Setting:

In these portions of the San Joaquin County, land usage is primarily **rural with single family homes**.

There are many large trees adjacent to the project area. Nesting and migratory birds, protected by the Migratory Bird Treaty Act, may nest within these trees. Furthermore, the Swainson's Hawk, a raptor species of concern within the State of California and listed as threatened may nest adjacent to or within the project area. A pre-construction survey for nesting Swainson's Hawks and other migratory birds is recommended if construction is scheduled to occur from February 15th to September 1st.

Beneficiaries:

The public will see increased safety and fewer hazards with these well-maintained roads. Overall, there will be reduced maintenance concerns and more reliability within the project area.



District No. 4

NO SCALE

