

By Deputy: cperezsuarez

NOTICE OF EXEMPTION



TO: Office of Planning and Research
CEQAnet Web Portal
<https://ceqasubmit.opr.ca.gov/>

FROM: San Joaquin County
Department of Public Works
1810 East Hazelton Avenue
Stockton, California 95205

County Clerk
County of San Joaquin California
44 North San Joaquin Street, Suite 260
Stockton, California 95202

Project Title: Oakwood Road Area Streets Resurfacing

Project Location: See attached vicinity map

Description of Nature, Purpose, and Beneficiaries: See attached project description

Public Agency Approving Project: San Joaquin County Public Works Department

Name of Agency Carrying Out Project: San Joaquin County Public Works Department

This is to advise that the San Joaquin County Public Works Department has approved the above described project on 3/11/2026 and has made the determination that the project is exempt due to the following:

Exempt Status (check one):

- Ministerial (Sec. 21080 (b) (1); 15268)
- Declared Emergency (Sec. 21080 (b) (3); 15269(a))
- Emergency Project (Sec. 21080 (B) (4); 15269(b) (c))
- Categorical Exemption: Existing Facilities (Sec. 15301 (c))
- Statutory Exemption (Sec. 15282(l))

Reason(s) why project is exempt: The project will repair existing roads and will not result in any major alterations to the configuration of the roads. No additional vehicle travel lanes will be constructed.

Lead Agency Contact Person: Fatima Gutierrez, Associate Planner, (209) 468-3035

Signature: Fatima Gutierrez Title: Associate Planner Date: 3/18/2026

OAKWOOD ROAD AREA STREETS RESURFACING

Project Description

Project Location:

Oakwood Road: Nelson Road to Van Allen Road; **Amerigo Road:** south end to Oakwood Road; **Nelson Road:** Gawne Road to north end; **Stow Avenue:** Gawne Road to north end. **See attached Vicinity Map.**

Project Justification:

Oakwood Road's original construction date and method are unknown. Oakwood Road is a 20-foot-wide local road, that was chip sealed in 2009 and 2019 and had a restoration in the year 2020. The Average Daily Traffic (ADT) is 164 and the 2024 Overall Condition Index (OCI) rating is 66.18. Amerigo Road's original construction date and method unknown. Amerigo Road is a 12-foot-wide local road and was last chip sealed in 2019. The ADT is unknown and the 2024 OCI rating is 28.96. Nelson Road's original construction date and method are unknown. Nelson Road is a 22-foot-wide local road that was chip sealed in 2011 and 2019. The ADT is 27 and the 2024 OCI rating is 43.85. Stow Avenue's original construction date and method are unknown. Stow Avenue is a 14-16-foot-wide local road that was last chip sealed in 2019. The ADT is unknown and the 2024 OCI rating is 38.57.

Oakwood Road Area Streets consists of 4 roadways with extensive areas of alligator and longitudinal cracking along with severe rutting on Stow Avenue. Amerigo Road and Stow Avenue have isolated areas of ponding along the shoulder that are encroaching onto the roadways.

Scope of Work:

The project will consist of:

1. Placing 0.17 feet of Hot Mix Asphalt (HMA) (Type A) on Amerigo Road, Nelson Road and Oakwood Road: (14-24 feet wide).
2. Pulverizing and recompacting 0.25 feet of existing roadway and placing 0.25 feet of HMA on Stow Avenue.
3. Repairing Pavement structural failure areas on Amerigo Road, Nelson Road and Oakwood Road with full depth 0.25 feet of HMA (Type A).
4. Replenishing shoulders with 4-foot-wide shoulder backing: 2 feet at (8%) and 2 feet to conform.
5. Constructing HMA (Type D & Type E) Driveways.
6. Adjusting 2 existing survey monument frames and covers on Nelson Road to finished grade.
7. Applying Penetration Treatment at all intersection radii plus 50 feet or to conform.
8. Repairing eroded shoulder at existing 30-inch Reinforced Concrete Pipe (RCP) on Stow Avenue.
9. Performing Earthwork (Miscellaneous Areas) where water ponds along the roadway Edge of Pavement (EP).

Environmental Setting:

In these portions of the San Joaquin County, land usage is primarily **rural with single family homes.**

There are many large trees adjacent to the project area. Nesting and migratory birds, protected by the Migratory Bird Treaty Act, may nest within these trees. Furthermore, the Swainson's Hawk, a raptor species of concern within the State of California and listed as threatened may nest adjacent to or within


OAKWOOD ROAD AREA STREETS RESURFACING

Project Description


the project area. A pre-construction survey for nesting Swainson's Hawks and other migratory birds is recommended if construction is scheduled to occur from February 15th to September 1st.

Beneficiaries:

The public will see increased safety and fewer hazards with these well-maintained roads. Overall, there will be reduced maintenance concerns and more reliability within the project area.



District No. 4 NO SCALE



Vicinity Map
OAKWOOD ROAD AREA
STREETS RESURFACING
 Amerigo Road: South End to Oakwood Road
 Nelson Road: Gawne Road to North End
 Oakwood Road: Nelson Road to Van Allen Road
 Stow Avenue: Gawne Road to North End

