

NOTICE OF EXEMPTION

By Deputy: samanthat1



TO: ☒ Office of Planning and Research
CEQAnet Web Portal
<https://ceqasubmit.opr.ca.gov/>

FROM: San Joaquin County
Department of Public Works
1810 East Hazelton Avenue
Stockton, California 95205

☒ County Clerk
County of San Joaquin California
44 North San Joaquin Street, Suite 260
Stockton, California 95202

Project Title: Kingdon and Neeley Road Resurfacing

Project Location: See attached vicinity map

Description of Nature, Purpose, and Beneficiaries: See attached project description

Public Agency Approving Project: San Joaquin County Public Works Department

Name of Agency Carrying Out Project: San Joaquin County Public Works Department

This is to advise that the San Joaquin County Public Works Department has approved the above described project on 5/1/2025 and has made the determination that the project is exempt due to the following:

Exempt Status (check one):

- ☐ Ministerial (Sec. 21080 (b) (1); 15268)
☐ Declared Emergency (Sec. 21080 (b) (3); 15269(a))
☐ Emergency Project (Sec. 21080 (B) (4); 15269(b) (c))
☒ Categorical Exemption: Existing Facilities (Sec. 15301 (c))
☐ Statutory Exemption (Sec. 15282(l))

Reason(s) why project is exempt: The project will repair existing roads and will not result in any major alterations to the configuration of the roads. No additional vehicle travel lanes will be constructed.

Lead Agency Contact Person: Marilissa Loera, Senior Planner, (209) 468-3085

Signature:  Title: Senior Planner Date: 5/12/2025

KINGDON AND NEELEY ROAD RESURFACING

Project Description

Project Location:

Kingdon Road: Thornton Road to Neeley Road, Neeley Road to De Vries Road; **Neeley Road:** Tredway Road to Kingdon Road; **Royal Road:** Kingdon Road to South End. **See attached Vicinity Map.**

Project Justification:

The roadways were originally constructed as part of the Lodi Colony Tract in 1905, structural section is not available. Kingdon Road and Royal Road were chip sealed in the 2007-2008 Road Maintenance Chip Cycle. Kingdon Road, Neeley Road, and Royal Road were chip sealed in the 2017-2018 Road Maintenance Chip Cycle.

The existing roadway surfaces within the project limits have significant alligator and block cracking and isolated areas of rutting, with Overall Condition Index (OCI) ratings ranging from 20-31. There are significant ponding issues at isolated locations impacting the surface as well as a failing cross drain pipe that will be replaced.

Scope of Work:

The project will consist of:

1. Placing 0.25 feet of Hot Mix Asphalt (HMA) Overlay on Kingdon Road (Thornton Road to De Vries Road), Neeley Road (Tredway Road to Kingdon Road), and Royal Road (South End to Kingdon Road).
2. Repairing pavement structural failure areas with full depth 0.25-0.50 feet of HMA (Type A).
3. Performing Earthwork (Miscellaneous Areas) in segments identified by Road Maintenance as ponding areas.
4. Placing four (4) Monument frames and covers as requested by the Professional Land Surveyor (PLS).
5. Placing 4-6 feet HMA driveways.
6. Replacing the 12-inch Corrugated Steel Pipe (CSP) cross drain pipe on Kingdon Road approximately 20 feet west of Royal Road.
7. Adding 12-inch CSP drain pipe across Neeley Road at the intersection of Neeley & Tredway Road, to equalize storm drain ditches on either side.

Environmental Setting:

In these portions of the San Joaquin County, land usage is primarily **rural with single family homes.**


There are many large trees adjacent to the project area. Nesting and migratory birds, protected by the Migratory Bird Treaty Act, may nest within these trees. Furthermore, the Swainson's Hawk, a raptor species of concern within the State of California and listed as threatened may nest adjacent to or within the project area. A pre-construction survey for nesting Swainson's Hawks and other migratory birds is recommended if construction is scheduled to occur from February 15th to September 1st.

Beneficiaries:

KINGDON AND NEELEY ROAD RESURFACING


Project Description

The public will see increased safety and fewer hazards with these well-maintained roads. Overall, there will be reduced maintenance concerns and more reliability within the project area.



D4

NO SCALE



Vicinity Map KINGDON AND NEELEY ROAD RESURFACING

Kingdon Rd: (Thorton Rd to Neeley Rd; Neeley Rd to De Vries Rd)
Neeley Rd: (Tredway Rd to Kingdon Rd)
Royal Rd: (Kingdon Rd to South End)

