

NOTICE OF EXEMPTION

By Deputy: kmchugh



TO: ☒ Office of Planning and Research  
CEQAnet Web Portal  
<https://ceqasubmit.opr.ca.gov/>

FROM: San Joaquin County  
Department of Public Works  
1810 East Hazelton Avenue  
Stockton, California 95205

☒ County Clerk  
County of San Joaquin California  
44 North San Joaquin Street, Suite 260  
Stockton, California 95202

Project Title: Davis Road Resurfacing

Project Location: See attached vicinity map

Description of Nature, Purpose, and Beneficiaries: See attached project description

Public Agency Approving Project: San Joaquin County Public Works Department

Name of Agency Carrying Out Project: San Joaquin County Public Works Department

This is to advise that the San Joaquin County Public Works Department has approved the above described project on 7/23/2025 and has made the determination that the project is exempt due to the following:

Exempt Status (check one):

- ☐ Ministerial (Sec. 21080 (b) (1); 15268)
- ☐ Declared Emergency (Sec. 21080 (b) (3); 15269(a))
- ☐ Emergency Project (Sec. 21080 (B) (4); 15269(b) (c))
- ☒ Categorical Exemption: Existing Facilities (Sec. 15301 (c))
- ☐ Statutory Exemption (Sec. 15282(l))

Reason(s) why project is exempt: The project will repair an existing road and will not result in any major alterations to the configuration of the road. No additional vehicle travel lanes will be constructed.

Lead Agency Contact Person: Fatima Gutierrez, Assistant Planner, (209) 468-3035

Signature: Fatima Gutierrez Title: Assistant Planner Date: 7/30/2025

## DAVIS ROAD RESURFACING

### Project Description

#### **Project Location:**

Davis Road from Peltier Road to North End. **See attached Vicinity Map.**

#### **Project Justification:**

Davis Road's original construction date and existing structural sections are unknown. The road has been periodically chip sealed by Road Maintenance with the most recent application occurring in 2019.

The existing roadway exhibits frequent transverse and longitudinal cracking throughout the project limits with minimal to no shoulder backing.

#### **Scope of Work:**

The project will consist of:

1. Resurfacing existing 21-foot-wide roadway with 0.25 feet of Hot Mix Asphalt (HMA). No paving fabric will be used.
2. Repairing all pavement structural failure areas with full depth 0.25 feet HMA.
3. Constructing HMA driveways and frontages 8 feet in length from edge of pavement.
4. Placing 4-foot-wide gravel shoulders on both sides: 2 feet (8% slope) and 2 feet to conform.
5. Applying Penetration Treatment at all intersection radii plus 50 feet or to conform.
6. Professional Land Surveyor (PLS) verifying monuments in the field and advising placement of one new survey monument box to finished grade.


#### **Environmental Setting:**

In these portions of the San Joaquin County, land usage is **rural with single family homes.**

**There are many large trees adjacent to the project area.** Nesting and migratory birds, protected by the Migratory Bird Treaty Act, may nest within these trees. Furthermore, the Swainson's Hawk, a raptor species of concern within the State of California and listed as threatened may nest adjacent to or within the project area. A pre-construction survey for nesting Swainson's Hawks and other migratory birds is recommended if construction is scheduled to occur from February 15<sup>th</sup> to September 1<sup>st</sup>.

#### **Beneficiaries:**


The public will see increased safety and fewer hazards with this well-maintained road. Overall, there will be reduced maintenance concerns and more reliability within the project area.



D4

D4

NO SCALE



# Vicinity Map **DAVIS ROAD RESURFACING** ( Peltier Road to North End )

