

By Deputy: aambriz



## NOTICE OF EXEMPTION

TO: ☒ Office of Planning and Research  
CEQAnet Web Portal  
<https://ceqasubmit.opr.ca.gov/>

FROM: San Joaquin County  
Department of Public Works  
1810 East Hazelton Avenue  
Stockton, California 95205

☒ County Clerk  
County of San Joaquin California  
44 North San Joaquin Street, Suite 260  
Stockton, California 95202

Project Title: Frisbee Lane and Wayne Court Resurfacing

Project Location: See attached vicinity map

Description of Nature, Purpose, and Beneficiaries: See attached project description

Public Agency Approving Project: San Joaquin County Public Works Department

Name of Agency Carrying Out Project: San Joaquin County Public Works Department

This is to advise that the San Joaquin County Public Works Department has approved the above described project on 9/11/2026 and has made the determination that the project is exempt due to the following:

Exempt Status (check one):

- ☐ Ministerial (Sec. 21080 (b) (1); 15268)
- ☐ Declared Emergency (Sec. 21080 (b) (3); 15269(a))
- ☐ Emergency Project (Sec. 21080 (B) (4); 15269(b) (c))
- ☒ Categorical Exemption: Existing Facilities (Sec. 15301 (c))
- ☐ Statutory Exemption (Sec. 15282(l))

Reason(s) why project is exempt: The project will repair existing roads and will not result in any major alterations to the configuration of the roads. No additional vehicle travel lanes will be constructed.

Lead Agency Contact Person: Fatima Gutierrez, Associate Planner, (209) 468-3035

Signature: Fatima Gutierrez Title: Associate Planner Date: 9/30/2026

## **FRISBEE LANE AND WAYNE COURT RESURFACING**

### **Project Description**

#### **Project Location:**

**Frisbee Lane:** McKinley Avenue to Watters Road; **Wayne Court:** South End to Frisbee Lane. **See attached Vicinity Map.**

#### **Project Justification:**

The original construction date and method of the roads for this project are unknown. Per survey records, the west half of Frisbee Lane was shown as an unnamed 40-foot right-of-way in 1944. The east half of Frisbee Lane and Wayne Court were constructed as part of the Blue Grass Estates subdivision in 1978. The roads have been periodically chip sealed by Road Maintenance with the most recent application occurring in 2018.

The existing pavement has a fair amount of surface cracking (block, transverse, longitudinal, alligator), minor distortion in wheel tracks and isolated areas of structural failure.

#### **Scope of Work:**

The project will consist of:

1. Resurfacing existing roadways (22-32 feet wide on Frisbee Lane, 32 feet wide to a cul-de-sac on Wayne Court) with 0.17 feet of Hot Mix Asphalt (HMA). No paving fabric will be used.
2. Repairing all pavement structural failure areas with full depth 0.50 feet of HMA.
3. Constructing HMA driveways and frontages 8 feet in length from edge of pavement.
4. Placing 4 feet wide gravel shoulders on both sides: 2 feet (8% slope) and 2 feet to conform.
5. Apply Penetration Treatment at all intersection radii plus 50' or to conform.
6. Professional Land Surveyor verifying monuments in the field and advising placement of four (4) survey monument boxes and adjusting two (2) survey monument boxes to finished grade.

#### **Environmental Setting:**

In these portions of the San Joaquin County, land usage is primarily **rural with single family homes.**

**There are many large trees adjacent to the project area.** Nesting and migratory birds, protected by the Migratory Bird Treaty Act, may nest within these trees. Furthermore, the Swainson's Hawk, a raptor species of concern within the State of California and listed as threatened may nest adjacent to or within the project area. A pre-construction survey for nesting Swainson's Hawks and other migratory birds is recommended if construction is scheduled to occur from February 15<sup>th</sup> to September 1<sup>st</sup>.

#### **Beneficiaries:**

The public will see increased safety and fewer hazards with these well-maintained roads. Overall, there will be reduced maintenance concerns and more reliability within the project area.

