

NOTICE OF EXEMPTION

TO: X Office of Planning and Research
CEQAnet Web Portal
<https://ceqasubmit.opr.ca.gov/>

FROM: San Joaquin County
Department of Public Works
1810 East Hazelton Avenue
Stockton, California 95205

X County Clerk
County of San Joaquin California
44 North San Joaquin Street, Suite 260
Stockton, California 95202

Project Title: Bruella Road and Peltier Road Resurfacing

Project Location: See attached vicinity map

Description of Nature, Purpose, and Beneficiaries: See attached project description

Public Agency Approving Project: San Joaquin County Public Works Department

Name of Agency Carrying Out Project: San Joaquin County Public Works Department

This is to advise that the San Joaquin County Public Works Department has approved the above described project on 9/4/2026 and has made the determination that the project is exempt due to the following:

Exempt Status (check one):

- ☐ Ministerial (Sec. 21080 (b) (1); 15268)
☐ Declared Emergency (Sec. 21080 (b) (3); 15269(a))
☐ Emergency Project (Sec. 21080 (B) (4); 15269(b) (c))
☒ Categorical Exemption: Existing Facilities (Sec. 15301 (c))
☐ Statutory Exemption (Sec. 15282(l))

Reason(s) why project is exempt: The project will repair existing roads and will not result in any major alterations to the configuration of the roads. No additional vehicle travel lanes will be constructed.

Lead Agency Contact Person: Fatima Gutierrez, Associate Planner, (209) 468-3035

Signature: Fatima Gutierrez Title: Associate Planner Date: 10/12/2026

Filed Doc #: 39-10132026-306
Tue Oct 13 12:33:04 PDT 2026
Page: 1 of 4 Fee: \$50.00
Steve J. Bestolarides
San Joaquin County Clerk

By Deputy: aambriz



BRUELLA ROAD AND PELTIER ROAD RESURFACING

Project Description

Project Location:

Bruella Road: Peltier Road to Acampo Road; **Peltier Road:** 99 Frontage Road East to Bruella Road. See attached Vicinity Map.

Project Justification:

Peltier Road was constructed in 1930 (16 feet wide by 1 inch oiled top course over 5-inch base course). Peltier was widened by County maintenance forces from 16 feet to 22 feet, structural section and date is unknown. Peltier (22 feet wide) was resurfaced in 1970 with 0.25 feet of asphalt concrete. Since then, County maintenance forces have placed periodic chip seals. The roadway was widened from 22 feet to 24 feet and resurfaced in 2002. Peltier Road was most recently crack sealed in 2025 from State Route 99 to Bruella Road. Bruella Road's construction date is unknown. In 2002 Bruella Road was resurfaced with 0.25 feet overlay.

Within the specified project limits, the prevailing condition of the pavement surface is characterized by potholes and cracking.

Scope of Work:

The project will consist of:

1. Resurfacing existing roadway Bruella (22 feet wide) and Peltier (28 feet wide) with 0.25 feet Hot Mix Asphalt (Type A).
2. Constructing tapered HMA edges to protect the edge of pavement.
3. Repairing pavement structural failure areas with full depth 0.50 feet of Hot Mix Asphalt (HMA) (Type A).
4. Replenishing the existing graveled shoulders with 4 to 6-foot-wide Shoulder Backing, comprising 2 feet to 4 feet at an 8% slope and 2 feet designed to conform.
5. Performing earthwork where the shoulder's elevation is higher than the pavement.
6. Applying Penetration Treatment along the inside of the curves and at all intersection radii plus 50 feet or to conform.
7. Constructing 8 feet HMA (Type A) driveways.
8. Removing and replacing existing cross pipe: 12-inch Corrugated Metal Pipe (CMP) located in Peltier Road 1,177 feet west of Bruella Road.
9. Installing side-road ditches in some areas to improve drainage.

Environmental Setting:

In these portions of the San Joaquin County, land usage is primarily **agricultural**.


There are many large trees adjacent to the project area. Nesting and migratory birds, protected by the Migratory Bird Treaty Act, may nest within these trees. Furthermore, the Swainson's Hawk, a raptor species of concern within the State of California and listed as threatened may nest adjacent to or within the project area. A pre-construction survey for nesting Swainson's Hawks and other migratory birds is recommended if construction is scheduled to occur from February 15th to September 1st.

BRUELLA ROAD AND PELTIER ROAD RESURFACING

Project Description


Beneficiaries:

The public will see increased safety and fewer hazards with these well-maintained roads. Overall, there will be reduced maintenance concerns and more reliability within the project area.



District 4

NO SCALE



Vicinity Map
Bruella Road And Peltier Road Resurfacing
Bruella Road: Peltier Road to Acampo Road
Peltier Road: Bruella Road to State Route 99

