

Community Development Department

Planning · Building · Code Enforcement · Fire Prevention

Jennifer Jolley, Director

FIRE HAZARD REDUCTION GUIDELINES

The following guide will assist you in complying with the requirements of the weed abatement program of San Joaquin County and make your property "Fire Safe".

FIRE HAZARD: (Defined for the purpose of weed abatement). Generally, any dry grasses, weeds, or rubbish that when exposed to an ignition source, could ignite and threaten or prove harmful to life, property, and or the environment.

FIRE HAZARD REDUCTION: DRY GRASSES, WEEDS, OR RUBBISH, WHICH HAVE BEEN DEEMED A FIRE HAZARD, SHALL BE ABATED AND KEPT ABATED THROUGHOUT THE FIRE SEASON. The time period designated as "THE FIRE SEASON" is **year-round**.

A DEFENDABLE SPACE shall be created around all structures, and other combustible properties and property lines, using one or more of the acceptable methods outlined below. Defendable Space is an area immediately adjacent to combustible properties, which has been cleared of combustibles, dry grasses, and weeds, to create and maintain a minimum firebreak.

The recognized **MINIMUM FIREBREAK** is generally as follows:

Properties LESS than 2 acres: The entire property to be abated.

Properties MORE than 2 acres: 100 ft. firebreak around all structures and property lines. It is the

option of the Fire District to abate the whole property when surrounding exposure warrants it. If you are in question, please

contact your fire district.

Pasture or Farm Land: 15 ft. firebreak around property lines and 100 ft. around all

structures and combustible exposures, (haystacks, barns, etc).

Property owners are required to provide large firebreaks on properties that have limited access, insufficient water supply and contain a high fire load.

Note: The San Joaquin County Board of Supervisors has also adopted an ordinance requiring the property owner to maintain the public right-of-way adjacent to their property, free of fire hazards.

Acceptable methods of making firebreaks:

Discing or Rototilling: (Preferred Method) Grasses and weeds may be disced or rototilled to reduce the hazard or to create a firebreak. Laying the weeds over with a drag device **is not** acceptable.

Cutting/Mowing: Grasses and weeds that have been cut or mowed must be REMOVED or SPREAD so as not to present a fire hazard and the remaining vegetation growth shall be maintained at <u>"NO HIGHER THAN 4 INCHES"</u>.

PROPERTIES WITH LIVESTOCK: Grasses and weeds may be abated by the use of livestock. However, all other firebreaks and defendable space guidelines still apply. A <u>15 ft. firebreak around property lines is required</u>, and it is still the option of the Fire District to abate weeds on properties where the amount of animals on the property could not maintain a reasonably safe fire condition. If you have questions, please contact your local fire district.