SAN JOAQUIN COUNTY EMERGENCY MEDICAL SERVICES AGENCY

TITLE: Med Net Radio Communications Plan

PURPOSE:

The purpose of this policy is to define the use of each Med Net radio channel.

AUTHORITY:

Health and Safety Code, Division 2.5, Section 1797.220, 1798 et seq.; Title 47 Code of Federal Regulations, Part 90, Section 90.20 (a)(1)(iii), (a)(2)(xiii), (c)(3) and (d)(66)(i).

POLICY:

- I. Prehospital personnel will communicate with hospitals using the following Med Net radio channels:
 - A. Channel 1 Adventist Health Lodi Memorial (Receiving Hospital)
 - B. Channel 2 San Joaquin General (Base and Receiving Hospital)
 - C. Channel 3 Kaiser Hospital Manteca (Receiving Hospital)
 - D. Channel 4 Sutter Tracy Community (Receiving Hospital)
 - E. Channel 5 Doctor's Hospital of Manteca (Receiving Hospital)
 - F. Channel 6 Disaster Control Facility
 - G. Channel 7 Dameron (Receiving Hospital)
 - H. Channel 8 St. Joseph's Medical Center (Receiving Hospital)
- II. Channel 6 will only be used for prehospital to Disaster Control Facility communications during multi-casualty incidents, including MCI pre-alert notifications.
- III. San Joaquin County Med Net channels 1 through 8 are required to be programmed in accordance with Table 1.

Effective:	July
Supersedes:	-

y 1, 2025 rigila ily; 2022 atherine Shafer, MD

Approved:

Medical Director

DocuSigned by: 06A07EEDBDA14D4... Page 1 of 2

EMS Administrator

SAN JOAQUIN COUNTY EMERGENCY MEDICAL SERVICES AGENCY



EMS Policy No. 3400

TITLE: Med Net Radio Communications Plan

Ch #	Function	Channel Name/Trunked Radio System Talkgroup	Assignment	RX Freq N or W	RX Tone/NAC	TX Freq N or W	TX Tone/NAC	Mode (A, D, or M)	Remarks
1	Hospital Contact	Med 1	Adventist Health Lodi Memorial	463.0000 (N)	DPL 132	468.0000 (N)	DPL 132	A	
2	Hospital Contact and Base Orders	Med 2	San Joaquin General Hospital	463.0250 (N)	162.2 (5B)	468.0250 (N)	162.2 (5B)	A	Countywide coverage
3	Hospital Contact	Med 3	Kaiser Hospital Manteca	463.0500 (N)	DPL 331	468.0500 (N)	DPL 331	A	
4	Hospital Contact	Med 4	Sutter Tracy Comm Hospital	463.0750 (N)	162.2 (5B)	468.0750 (N)	162.2 (5B)	A	
5	Hospital Contact	Med 5	Doctor's Hospital of Manteca	463.1000 (N)	DPL 532	468.1000 (N)	DPL 532	A	
6	MCI Communications	Med 6	Disaster Control Facility Contact	463.1250 (N)	162.2 (5B)	468.1250 (N)	162.2 (5B)	A	Countywide coverage
7	Hospital Contact	Med 7	Dameron Hospital	463.1500 (N)	DPL 732	468.1500 (N)	DPL 732	A	
8	Hospital Contact	Med 8	St. Joseph's Medical Center	463.1750 (N)	162.2 (5B)	468.1750 (N)	162.2 (5B)	А	
Channel Naming Convention: 1. Lodi Memorial 2. S L General									

2. SJ General

Kaiser Manteca
Sutter Tracy
Doctors Manteca

6. SJ Control

7. Dameron 8. St. Josephs

Effective:	July 1, 2025		Page 2 of 2
Supersedes:	Manuale 1, 2022	DocuSigned by:	
	Katherine Shafer, MD		
Approved:		06A07EEDBDA14D4	
	Medical Director	EMS Administrator	_