TITLE: BLS Seizures EMS Policy No. 5531

# San Joaquin County Emergency Medical Services Agency

# **BLS Seizures**

**AUTHORITY**: Health and Safety Code, Division 2.5, Sections 1797.60, 1797.80, 1797.197, 1797.197a, 1797.204, 1797.220, 1798; California Code of Regulations, Title 22, Chapter 2, Sections 100062, 100063, 100064

## **INFORMATION NEEDED:**

Patient History: recent infection, fever, trauma, environment (heat/cold), epilepsy.

Current Seizure History: onset, duration, frequency, description of seizure.

Change in mental status: baseline status, onset and progression of altered state, symptoms prior to altered state such as headache, seizures, confusion, and trauma.

## **OBJECTIVE FINDINGS:**

Level of consciousness (AVPU) and neurological assessment.

Evidence of trauma.

High temperature (febrile state).

Current seizure activity.

Medical information tags, bracelets or medallions.

## TREATMENT:

- 1. Protect patient from further injury move furniture and ensure safe area for treatment.
- 2. Primary Survey ensures ABC's.
- 3. Spinal motion restrictions as indicated.
- 4. Ensure ALS Response.
- 5. Monitor SpO2.
- 6. Administer oxygen: Oxygen 10-15 L/min via non-rebreathing mask. Patients with ineffective respirations: support ventilations with BVM and airway.
- 7. Institute appropriate cooling measures if environmental hypothermia is suspected by history and findings.
- 8. Secondary Survey and Routine Medical Care.
- 9. Continually assess neurological status.
- 10. Enhanced Skills EMT: obtain blood glucose determination.
- 11. If blood glucose is less than 70 mg/dl, administer oral glucose according to EMS Policy No. 5530, <u>BLS Altered Mental Status</u>.

Note: Be prepared for recurrent seizures and do not forcibly restrain patient during seizure.

Effective: July 1, 2024 Page 1 of 2

Supersedes: April 1, 2020

Approved: Signature on file Signature on file

Medical Director EMS Administrator

TITLE: **BLS Seizures** EMS Policy No. **5531** 

Effective: July 1, 2024 Page 2 of 2

Supersedes: April 1, 2020

Approved: Signature on file Medical Director

Signature on file EMS Administrator