


CORNER RECORD

Document Number CR-99-12
County of San Joaquin, California

City of _____

Brief Legal Description TOWNSHIP CORNER - NORTHWEST CORNER SECTION 6, TOWNSHIP 4
SOUTH, RANGE 6 EAST, M.D.M.



CORNER TYPE

Government Corner Control
 Meander Property
 Rancho Other
 Date of Survey May 4, 1999

COORDINATES (Optional)

N. _____
 E. _____
 Zone _____ NAD27 NAD83
 NAD83 Epoch _____
 Elev. _____
 Vert. Datum: NGVD29 NAVD88
 Meas. Units: Metric Imperial

Corner - Left as found Found and tagged Established Reestablished Rebuilt

Identification and type of corner found: Evidence used to identify or procedure used to establish or reestablish the corner:
Reestablished by using reference points and swing as per Corner Record
No. 99-11.

A description of the physical condition of the monument as found and as set or reset: Set 2 1/2" Brass Cap
on a 3/4" X 36" Steel Rod in Monument Well with straddlers. Refer to the
backside of this sheet for monument stamping.

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with
the Land Surveyors' Act on July 2, 1999.

Signed [Signature] L.S. [Redacted] Number 4233



COUNTY SURVEYOR'S STATEMENT

This Corner Record was received JULY 28, 1999 and examined
and filed AUGUST 3, 1999.

Signed Henry M. Hirata R.C.E. No. 21258
Title County Surveyor



County Surveyor's Comment _____


(D.D. Sheet Nos. 67, 68, 76)

FD. R/R SPIKE FOR SECTION CORNER PER R.S. 16-14.

HWY 132

REFERENCE POINT FOUND SPIKE WITH TAG L.S. 4233.

CORNER DESTROYED BY ROAD RECONSTRUCTION. RESET TOWNSHIP CORNER POSITION BY USING THE REFERENCE POINTS AS PER CORNER RECORD NO. 99-11. SET PK NAIL MONUMENT STRADDLERS, MONUMENT BOX AND SET 2 1/2" BRASS CAP ON A 3/4" x 36" LONG STEEL ROD IN MONUMENT WELL. BRASS DISC IS STAMPED AS FOLLOWS:



BIRD ROAD

1/4 COR. LOST

S.25 S.30
S.36 S.31

30' 30'

MEASURED TIE
N 00°18'19" E 5288.28'
(N 00°18'19" E 5288.40')
CALC. TIE PER R.S. 16-14

1065.91'

N 00°20'35" W

SCALE: 1" = 40'

REFERENCE POINT - FOUND LEAD AND TACK, TAGGED L.S. 4233, ON THE S.E. CORNER OF CONCRETE ACCESS STRUCTURE FOR THE HETCHY PIPELINE.

STEEL FENCE POST

STEEL FENCE POST

FD. CONC MON LEANING OVER WESTERLY.

FD. 6"x6" CONCRETE MONUMENT WITH U.S.G.S. BENCH MARK BRASS DISC.

BLEWETT ROAD

20'
20'

N 31°28'29" E

148°10'56"

109.36'

DATA TABLE

MEAS SWING TIE	COUNTY SWING TIE AS PER FIELD BOOK 49-T, PAGE 9 9-16-53.
① 56.27'	56.30'
② 43.23'	43.20'
③ 31.06'	30.50'
④ 27.16' S 88°07'29" W	27.18'