

**CORNER RECORD**


Document Number 00-158  
County of San Joaquin, California

City of \_\_\_\_\_

Brief Legal Description City of Stockton Control Monument "6S-5" on east levee of the Stockton Diverting Canal, 10 feet +/- south of Stockton Terminal & Eastern Railroad tracks per Record of Survey 29-34.

**CORNER TYPE**

**COORDINATES (Optional)**



Government Corner  Control   
Meander  Property   
Rancho  Other   
Date of Survey February 8, 2000

N. 2,180,078.757 per R.S. 33-20  
E. 6,347,173.415 per R.S. 33-20  
Zone 3 NAD27  NAD83   
NAD83 Epoch (1991.35)  
Elev. \_\_\_\_\_  
Vert. Datum: NGVD29  NAVD88   
Meas. Units: Metric  Imperial

Corner - Left as found  Found and tagged  Established  Reestablished  Rebuilt

Identification and type of corner found: Evidence used to identify or procedure used to establish or reestablish the corner:  
City of Stockton Control Monument was destroyed during levee reconstruction. Reestablished per ties shown on Record of Survey 29-34.

A description of the physical condition of the monument as found and as set or reset: Found 3/4" iron pins per Parcel Map 7-139 and used as ties per Record of Survey 29-34. Set 2-1/2 inch diameter brass disk stamped "CITY OF STOCKTON SURVEY MONUMENT 6S-5 RESET 2/00 LS 7520", set in concrete on the east levee of the Stockton Diverting Canal, flush with existing ground.

**SURVEYOR'S STATEMENT**

This Corner Record was prepared by me or under my direction in conformance with the Land Surveyors' Act on February 8, 2000 .

Signed David W. Lanphear L.S. Number 7520



**COUNTY SURVEYOR'S STATEMENT**

This Corner Record was received February 28, 2000 and examined and filed March 6, 2000.

Signed Henry M. Thrata R.C.E. No. 21258  
Title County Surveyor

County Surveyor's Comment \_\_\_\_\_

(D.D. Sheet No. 32C )

FOUND 3/4" IRON PIN, NO TAG, PER P.M. 7-139 AND R.S. 29-34

S.T. & E. R.R.

FOUND 3/4" IRON PIN, NO TAG, PER P.M. 7-139 AND R.S. 29-34

SET 2-1/2" DIAMETER BRASS DISK IN CONCRETE PILLAR

( N 2,180,078.757  
E 6,347,173.415  
PER R.S. 33-20 )

N11°55'49"E 117.78'

N52°07'16"E 122.27'

DIVERTING  
CANAL

### NOTES:

1. DISTANCES SHOWN ARE GROUND DISTANCES
2. 2-1/2" DIAMETER BRASS DISK STAMPED "CITY OF STOCKTON SURVEY MONUMENT 6S-5 RESET 2/00 LS 7520"
3. R.S. DENOTES RECORD OF SURVEY, BOOK-PAGE, SAN JOAQUIN COUNTY RECORDS
4. P.M. DENOTES PARCEL MAPS, BOOK-PAGE SAN JOAQUIN COUNTY RECORDS

