

CORNER RECORD


Document number 00-244
County of San Joaquin, California

City of _____

Brief Legal Description PARCEL "A" OF RECORD OF SURVEY 25-22, SAN JOAQUIN
COUNTY RECORDS.

CORNER TYPE

COORDINATES (Optional)



Government Corner Control
Meander Property
Rancho Other
Date of Survey AUGUST 9, 2000

N. _____
E. _____
Zone NAD27 NAD83
NAD83 Epoch _____
Elev. _____
Vert. Datum: NGVD29 NAVD88
Meas. Units: Metric Imperial

Corner - Left as found Found and tagged Established Reestablished Rebuilt

Identification and type of corner found: Evidence used to identify or procedure used to establish or reestablish the corner:
FOUND SUFFICIENT RECORD CORNERS SHOWN ON BOOK 25 OF SURVEYS,
PAGE 22, CORNER RECORD 00-100, AND CORNER RECORD 00-102 TO
REESTABLISH THE MISSING CORNER.

A description of the physical condition of the monument as found and as set or reset:
SET 3/4" DIAMETER X 30" LONG IRON PIN TAGGED R.C.E. 14269
AT THE LOCATION NOTED ON THE CORNER RECORD.

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with
the Land Surveyors' Act on AUGUST 15, 2000.

Signed C. Chance Wong R.C.E. Number 14269



COUNTY SURVEYOR'S STATEMENT

This Corner Record was received AUGUST 24, 2000, and examined
and filed AUGUST 29, 2000.

Signed Manuel Lopez R.C.E. No. 28054
Title County Surveyor



County Surveyor's Comment _____

(D.D. Sheet No. 63)

S62°44'53"W
40.00'

F.D. 1" I. PIPE AT E.C.
TAGGED 2' DEEP L.S. 2239(A)

P. BOLT & WASHER
AT E.C. IN MON. BDX(C)

LEGEND:

- FOUND AS NOTED
- SET 3/4" x 30" I. PIN TAGGED R.C.E. 14269
- C.R. DENOTES CORNER RECORD
- R.S. DENOTES RECORD OF SURVEY

REFERENCES:

- (A) R.S. 25-22, S.J. CO. RECORDS
- (B) C.R. 00-100, S.J. CO. SURVEYOR'S RECORD
- (C) C.R. 00-102, S.J. CO. SURVEYOR'S RECORD

SANTA FE ROAD
S27°15'07"E 1856.60'(M)(A)
S27°15'07"E 2175.56'(M)(A)
S27°15'07"E 2175.56'(M)



0 200
(IN FEET)
1" = 200'

GRAPHIC SCALE

PARCEL A
R.S. 25-22

S.F.N.
SET I. PIN
TAGGED R.C.E. 14269

F.D. BOLT & WASHER
AT B.C. IN MON. BDX(B)

PARCEL B

318.96'(M)(A)

S.F.N.

S62°44'53"W
40.00'

CORNER RECORD



WONG ENGINEERS, INC.
PLANNING ENGINEERING SURVEYING
STOCKTON, CALIFORNIA
AUGUST 2000