


# CORNER RECORD

Document Number CR-08-187City of MantecaCounty of San Joaquin, CaliforniaBrief Legal Description West Quarter corner of Section 11, T. 2 S., R. 6 E.**CORNER TYPE**

Government Corner	<input checked="" type="checkbox"/>	Control	<input type="checkbox"/>
Meander	<input type="checkbox"/>	Property	<input type="checkbox"/>
Rancho	<input type="checkbox"/>	Other	<input type="checkbox"/>

Date of Survey Sep. 22, 2004**COORDINATES(Optional)**

N. \_\_\_\_\_  
E. \_\_\_\_\_  
Zone \_\_\_\_\_ NAD27 ☐ AD83 ☐  
NAD83 Epoch \_\_\_\_\_  
Elev. \_\_\_\_\_  
Vert. Datum: NGVD29 ☐ NADV88 ☐  
Meas. Units: Metric ☐ Imperial ☒

Corner - Left as found ☒ Found and tagged ☐ Established ☐ Reestablished ☐ Rebuilt ☐

Identification and type of corner found: Evidence used to identify or procedure used to establish or reestablish the corner:

Found 3/4" iron pin tagged RCE 14269 as shown as set on that Record of Survey, Book 29 of Surveys, Page 38 and also shown on that Final Map, Book 39 of Maps and Plats, Page 91.

A description of the physical condition of the monument as found and as set or reset: Corner found in good condition.

**SURVEYOR'S STATEMENT**

This Corner Record was prepared by me or under my direction in conformance with

the Land Surveyor's Act on July 25, 2008.Signed Daniel Skidmore P.L.S. or R.C.E. No.: 7126**COUNTY SURVEYOR'S STATEMENT**

This Corner Record was received AUGUST 8<sup>TH</sup> 2008 and examined  
and filed AUGUST 19<sup>TH</sup> 2008

Signed John G. May P.L.S. or R.C.E. No.: 6186Title DEPUTY COUNTY SURVEYOR

County Surveyor's Comment \_\_\_\_\_

(D.D. SHEET NO. 57)

## SURVEY REFERENCES

- (A) REFERS TO BOOK 29 OF SURVEYS AT PAGE 38, S.J.C.R.
- (B) REFERS TO BOOK 5 OF PARCEL MAPS AT PAGE 112, S.J.C.R.
- (C) REFERS TO BOOK 10 OF SURVEYS AT PAGE 200, S.J.C.R.

## LEGEND

- INDICATES FOUND 3/4"  $\phi$  IRON PIPE  
W/TAG L.S. 7126 AS SHOWN ON REF.  
(A) UNLESS NOTED OTHERWISE
- (M) INDICATES MEASURED WITH THIS SURVEY
- (A) INDICATES RECORD DATA PER REFERENCE  
NOTED
- S.J.C.R. INDICATES SAN JOAQUIN COUNTY RECORDS
- M&P INDICATES SAN JOAQUIN COUNTY MAPS  
AND PLATS
- P.M. INDICATES PARCEL MAPS
- S.F.N. INDICATES SEARCHED FOR NOTHING FOUND
- FD. INDICATES MONUMENT FOUND AS NOTED



SAN JOAQUIN COUNTY

39-M&P-91

N84°23'30"E 810.67'(M) 810.17'(A,B)  
673.90'(M) 673.45'(A)

WOODWARD AVENUE

50'

36-RS-63

FD. CHISELED  
"+" IN CONC.  
SEE REF. (A)

FD. 3/4" IRON PIPE  
NO TAG  
SEE REF. (C)

136.77'(M)  
136.72'(A)

FD. 3/4" IRON PIPE  
NO TAG  
SEE REF. (A)

FD. 3/4" IRON PIN  
TAGGED RCE 14269  
AT WEST 1/4 COR.  
SEE REF. (A)

N01°32'23"E 2705.26'  
SECTION LINE

SECTION LINE

N00°00'46"W 303.19'(M) 303.32'(A)

N07°10'13"E  
114.98'(M) 115.00'(A,C)

N07°10'13"E  
84.95'(M)

DRAWN A6

DATE 7/01/08

SCALE 1"=100'

JOB # 296K

DWG. 296K\_COR.REC.

## CORNER RECORD

BEING THE WEST QUARTER CORNER  
OF SECTION 11, TOWNSHIP 2  
SOUTH, RANGE 6 EAST, MOUNT  
DIABLO MERIDIAN  
SAN JOAQUIN CALIFORNIA



**ASSOCIATED  
ENGINEERING, INC.**

Surveying • Design • Planning

4206 TECHNOLOGY DRIVE  
MODESTO, CALIFORNIA 95356  
PH: (209) 545-3390 FAX: (209) 545-3875