


CORNER RECORD

Document Number CR-13-212
City of _____ County of San Joaquin, California

Brief Legal Description San Francisco Water District Monument T146+60



T3S, R6E, MDM

CORNER TYPE

Government Corner ☐ Control ☐
Meander ☐ Property ☐
Rancho ☐ Other ☒

Date of Survey May 20, 2013

COORDINATES(Optional)

N. _____
E. _____
Zone _____ NAD27 ☐ NAD83 ☐
NAD83 Epoch _____
Elev. _____
Vert. Datum: NGVD29 ☐ NADV88 ☐
Meas. Units: Metric ☐ Imperial ☒

Corner - Left as found ☐ Found and tagged ☐ Established ☐ Reestablished ☒ Rebuilt ☐

Identification and type of corner found: Evidence used to identify or procedure used to establish or reestablish the corner:

"T" Line monument T146+60, a 3.5" brass disk set in concrete, referenced in the index entitled

"Hetch Hetchy Water & Power, Moccasin to Tesla Portal R.O.W. Survey, Final Coordinate List".

Monument verified and witness corners established prior to construction.

For survey report, contact Survey Dept., 1 Lakeshore Dr., Moccasin, CA 95347.

Reset San Francisco Water District Monument from witness corners after construction.

A description of the physical condition of the monument as found and as set or reset: _____

Set a 2' X 6" concrete cylinder 2' below grade with a 3.5" aluminum cap stamped

"City and County of San Francisco H.H.W.S. STA: T14660 L.S. 8755 EL. 335.69"

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with

the Land Surveyor's Act on May 20, 2013.

Signed [Signature] P.L.S. or R.C.E. No.: 8755



COUNTY SURVEYOR'S STATEMENT

This Corner Record was received June 4, 2013 and examined

and filed _____.

Signed _____ P.L.S. or R.C.E. No.: 26994

Title County Surveyor

County Surveyor's Comment _____



SET A 2' X 6" CONCRETE CYLINDER WITH A
3-1/2" ALUMINUM CAP STAMPED CITY AND COUNTY
OF SAN FRANCISCO H.H.W.S., STA.T14660
L.S. 8755 EL.335.69'

N28°14'09"E 39.92'

SET 5/8" CAPPED REBAR
STAMPED "JACOBS CONTROL"

N69°02'26"W 149.62'

FOUND LEAD & TACK IN
CONCRETE AT BASE
OF TOWER

