


# CORNER RECORD

Document Number CR-13-261

City of (APN 129-010-03)

County of San Joaquin County, CaliforniaBrief Legal Description Found EBMUD Monument in Aqueduct R/W near Bacon Island RdSec. 15, T1N,  
R4E, MDM

## CORNER TYPE

Government Corner	<input type="checkbox"/>	Control	<input checked="" type="checkbox"/>
Meander	<input type="checkbox"/>	Property	<input type="checkbox"/>
Rancho	<input type="checkbox"/>	Other	<input type="checkbox"/>

Date of Survey February 14, 2013

## COORDINATES (Optional)

N.			
E.			
Zone	<u></u>	NAD27	<input type="checkbox"/>
NAD83 Epoch	<u></u>		
Elev.	<u></u>		
Vert. Datum:	NGVD29	<input type="checkbox"/>	NAVD88 <input type="checkbox"/>
Meas. Units:	Metric	<input type="checkbox"/>	Imperial <input checked="" type="checkbox"/>

Corner - Left as found ☐ Found and tagged ☐ Established ☐ Reestablished ☒ Rebuilt ☐

Identification and type of corner found: Evidence used to identify or procedure used to establish or reestablish the corner:

On 12/11/12 an existing East Bay Municipal Utility District (EBMUD) brass disk monument was found on top of a concrete structure marking the centerline of the existing aqueduct (and control for the R/W).

The structure was found to be settling and construction was initiated to stabilize it.

A description of the physical condition of the monument as found and as set or reset:

On 2/14/13, after the above construction project, a new 3 1/2" brass disc monument (as described on Pg. 2) was placed on top of the new structure in a new location on C/L using existing centerline control monuments on either side of the station.

Reference EBMUD Field Book 4477, Page 53 (Burke/Burke)

## SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with the Professional Land Surveyor's Act on July 29, 2013

Signed R. Lee Hixson P.L.S. or R.C.E. No. 4806

## COUNTY SURVEYOR'S STATEMENT

This Corner Record was received August 1, 2013and examined and filed August 22, 2013Signed Thomas M. Gau P.L.S. or R.C.E. No. 26994Title County Surveyor

County Surveyor's Comment: \_\_\_\_\_



HOLT

SAN JOAQUIN COUNTY

BACON ISLAND RD




DETAIL A:

3 1/2" Brass Disk

SPECIAL ANCHOR  
STRUCTURE

OLD STRUCTURE SHAPE  
PRIOR TO CONSTRUCTION



NOT TO SCALE

**LEGEND**

- ⊙ FOUND MONUMENT  
(AS DESCRIBED)
- ⊙ SET MONUMENT  
(AS DESCRIBED)

APN  
129-200-35

C/L AQUEDUCT #1

89.25'

WIDTH  
VARIES

SET 3 1/2" BRASS DISK  
STAMPED AS SHOWN IN DETAIL A  
(RESET POST CONSTRUCTION)

APN  
129-200-39

FOUND 2 1/2" BRASS DISK  
STAMPED "EBMUD STA P2446+75.40"  
(DESTROYED BY CONSTRUCTION)

50'

50'

APN  
129-200-35

EBMUD  
MOKELUMNE AQUEDUCT RM  
(WIDTH VARIES)  
APN 129-010-03

1832.97'



FOUND 2 1/2" BRASS DISK  
STAMPED "EBMUD STA  
P2428+54.83" ON CONCRETE  
ANCHOR STRUCTURE MARKING  
C/L AQUEDUCT #1

ADDRESS: BACON ISLAND RD  
APN: 129-010-03

CR#

CR