


CORNER RECORD

Document Number CR-15-286

City of _____

County of SAN JOAQUIN, California

Brief Legal Description CENTER 1/4 CORNER OF SECTION 3 OF T3N, RTE



CORNER TYPE

Government Corner Control
Meander Property
Rancho Other

Date of Survey 10/19/15

COORDINATES(Optional)

N. _____
E. _____
Zone _____ NAD27 NAD83
NAD83 Epoch _____
Elevation _____
Vert. Datum: NGVD29 NAV88
Meas. Units: Metric Imperial

Corner - Left as found Found and tagged Established Reestablished Rebuilt

Identification and type of corner found: Evidence used to identify or procedure used to establish or reestablish the corner:

FOUND CENTER 1/4 CORNER OF SECTION 3 OF T3N, RTE AT THE INTERSECTION OF STATE ROUTE 17 AND LOCUST TREE ROAD AS PER CORNER RECORD DOCUMENT # 14-18

A description of the physical condition of the monument as found and as set or reset: FOUND 3/4" DIA. IRON ROD W/1 3/4" WASHER, SIMILAR TO STANDARD SAN JOAQUIN CO. MONUMENT, IN NEW MONUMENT WELL. MONUMENT WAS LOOSE AND APPEARS TO HAVE BEEN DISTURBED. RESET NEW 1" ID IRON PIPE W/YELLOW PLASTIC PLUG STAMPED "CALIF DOT" DOWN 0.45' INSIDE OF NEW MONUMENT WELL USING 3 FOUND REFERENCE POINTS FROM PREVIOUS CORNER RECORD.

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with the Land Surveyor's Act on 11/18, 2015.

Signed [Signature] (P.L.S. or R.C.E. Number 8022)
For the State of California
Department of Transportation


COUNTY SURVEYOR'S STATEMENT

This Corner Record was received November 18, 2015 and examined and filed December 18, 2015.

Signed [Signature] P.L.S. or R.C.E. Number 4842

Title Acting County Surveyor

County Surveyor's Comment _____





FOUND PK NAIL WITH
BRASS WASHER STAMPED
"CALTRANS" IN
TELEPHONE POLE
PER CR-06-11.

FOUND PK NAIL WITH
BRASS WASHER STAMPED
"CALTRANS" IN
TELEPHONE POLE
PER CR-06-11.

STATE ROUTE 12

* NOTE: PREVIOUS CORNER
RECORD SHOWS 45.13'
OBVIOUS ERROR IN
PREVIOUS MEASUREMENT

SET 1" I.D. IRON
PIPE W/ YELLOW
PLASTIC PLUG
STAMPED "CALIF DOT"
DOWN 0.45' BELOW
AC SURFACE IN
MONUMENT WELL

LOCUST TREE ROAD

FOUND PK NAIL WITH
BRASS WASHER STAMPED
"CALTRANS" IN
JOINT-USE POLE
PER CR-06-11.

NOTE: THE TIES SHOWN HEREON ARE FOR THE PURPOSE OF PERPETUATING AND RE-ESTABLISHING THE MONUMENTATION CURRENTLY EXISTING. NO ATTEMPT WAS MADE TO DETERMINE THE VALIDITY OF THE MONUMENT OR IT'S PROPER LOCATION IN RELATION TO LEGAL BOUNDARY LINES IN THE AREA.

