


CORNER RECORD

Document Number CR-15-287

City of _____

County of SAN JOAQUIN, California

Brief Legal Description EAST 1/4 CORNER OF SECTION 3 OF T3N, RTE



T3N RTE

CORNER TYPE

Government Corner Control
Meander Property
Rancho Other

Date of Survey 10/19/15

COORDINATES(Optional)

N. _____
E. _____
Zone _____ NAD27 NAD83
NAD83 Epoch _____
Elevation _____
Vert. Datum: NGVD29 NAV88
Meas. Units: Metric Imperial

Corner - Left as found Found and tagged Established Reestablished Rebuilt

Identification and type of corner found: Evidence used to identify or procedure used to establish or reestablish the corner:

FOUND EAST 1/4 CORNER OF SECTION 3 OF T3N, RTE PER RECORD OF SURVEYS VOL. 12, PAGE 160 AND CORNER RECORD DOCUMENT #06-10 AT THE INTERSECTION OF STATE ROUTE 12 AND KROLL ROAD.

A description of the physical condition of the monument as found and as set or reset: FOUND 3/4" DIA.

IRON ROD WITH NO TAG DOWN 0.3' INSIDE OF NEW MONUMENT WELL. FOUND ONE EXISTING REFERENCE POINT AND VERIFIED DISTANCE TO MONUMENT. SET TWO NEW REFERENCE POINTS AND MEASURED DISTANCES TO MONUMENT.

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with the Land Surveyor's Act on 11/18, 2015.

Signed [Signature] (P.L.S.) or R.C.E. Number 8022
For the State of California
Department of Transportation



COUNTY SURVEYOR'S STATEMENT

This Corner Record was received November 18, 2015 and examined and filed December 18, 2015.

Signed [Signature] P.L.S. or R.C.E. Number 4842

Title Acting County Surveyor

County Surveyor's Comment _____





SET PK NAIL WITH BRASS WASHER STAMPED "CALTRANS" IN JOINT USE POLE

KROLL ROAD

SET PK NAIL WITH BRASS WASHER STAMPED "CALTRANS" IN JOINT USE POLE

96.59'

37.81'

STATE ROUTE 12

100.03
100.05' meas.

FOUND PK NAIL WITH BRASS WASHER STAMPED "CALTRANS" IN POWER POLE PER CR-06-101

FOUND 3/4" DIA. IRON ROD WITH NO TAG DOWN 0.3' INSIDE NEW MONUMENT WELL.

NOTE: THE TIES SHOWN HEREON ARE FOR THE PURPOSE OF PERPETUATING THE MONUMENTATION CURRENTLY EXISTING. NO ATTEMPT WAS MADE TO DETERMINE THE VALIDITY OF THE MONUMENT OR IT'S PROPER LOCATION IN RELATION TO LEGAL BOUNDARY LINES IN THE AREA.