


CORNER RECORD

Document Number CR-16-63

City of Stockton

County of San Joaquin, California

Brief Legal Description Colonial West, Unit No. 2, Volume 19 of Maps & Plats, Page 52 and Colonial West, Unit No. 4, Volume 19 of Maps & Plats, Page 71.

| CORNER TYPE | | COORDINATES(Optional) | |
|---|--|--|---|
|  | Government Corner <input type="checkbox"/> | Control <input type="checkbox"/> | N. _____ |
| | Meander <input type="checkbox"/> | Property <input checked="" type="checkbox"/> | E. _____ |
| | Rancho <input type="checkbox"/> | Other <input checked="" type="checkbox"/> | Zone <u>III</u> NAD27 <input type="checkbox"/> NAD83 <input checked="" type="checkbox"/> |
| | | | NAD83 Epoch <u>1991.35</u> |
| | | | Elev. _____ |
| | Date of Survey <u>October 26, 2015</u> | | Vert. Datum: NGVD29 <input type="checkbox"/> NADV88 <input checked="" type="checkbox"/> |
| | | | Meas. Units: Metric <input type="checkbox"/> Imperial <input checked="" type="checkbox"/> |

T. 2 N., R. 6 E., M.D.B.&M.

Corner - Left as found Found and tagged Established Reestablished Rebuilt


Identification and type of corner found: Evidence used to identify or procedure used to establish or reestablish the corner:


Used G.P.S. to locate the centerline monuments. Found cut "X"s at lot line projections and used total station set up on centerline monuments to establish location of each found cut "X".

A description of the physical condition of the monument as found and as set or reset: _____


Found cut "X"s in concrete, along the approximate property line extended into the right of way, approximately 5 feet from lot corners. Also, found 3/4" iron pipes tagged R.C.E. 15831 in monument wells as shown on page 2.

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with the Land Surveyor's Act on October 29, 2015.
Signed  P.L.S. or R.C.E. No.: 7051



COUNTY SURVEYOR'S STATEMENT

This Corner Record was received January 11, 2016 and examined and filed February 9, 2016.
Signed  P.L.S. or R.C.E. No.: 4842



Title Acting County Surveyor

County Surveyor's Comment _____

STATEMENT OF PURPOSE:

THE PURPOSE OF THIS SURVEY IS TO IDENTIFY AND RECORD THE LOCATION OF EXISTING MONUMENTS PRIOR TO THE CONSTRUCTION OF PG&E FACILITIES AROUND THE MONUMENTS. THE PURPOSE OF THIS SURVEY IS NOT TO MAKE PROPERTY LINE DETERMINATIONS. LOT LINES SHOWN HEREON ARE FOR GENERAL LOCATION AND INFORMATIONAL PURPOSES ONLY.

LEGEND:

- ⊗ INDICATES FOUND CUT CROSS, NO TAG, NO REFERENCE.
- INDICATES FOUND 3/4" IRON PIPES IN WELL TAGGED R.C.E. 15831
- INDICATES SEARCHED FOR RECORD MONUMENT, NOT FOUND

DATUM STATEMENT:

COORDINATES SHOWN HEREON ARE GRID AND ARE BASED ON CITY OF STOCKTON MONUMENTS 4N-6 AND 4N-10, CALIFORNIA COORDINATE SYSTEM (CCS83), ZONE III, 1983 NAD, (1991.35 EPOCH STOCKTON & SAN JOAQUIN COUNTY GPS ADJUSTMENT) AND SHOWN ON RECORD OF SURVEY BOOK 33 OF SURVEYS, PAGE 20. THE PROJECT SPECIFIC COMBINED SCALE FACTOR IS 0.99994060.

NOTE:

FIELD EFFORT INCLUDED A SEARCH FOR EXISTING CUT CROSSES AT THEIR TYPICAL LOCATION, ONLY THOSE FOUND ARE SHOWN.

| GRID COORDINATES (U.S. SURVEY FEET) | | |
|-------------------------------------|-------------|-------------|
| POINT | NORTHING | EASTING |
| 2043 | 2196828.20' | 6318392.98' |
| 2050 | 2196971.76' | 6318657.61' |
| 2051 | 2196923.79' | 6318657.79' |
| 2072 | 2196805.75' | 6318229.47' |
| 2073 | 2196804.79' | 6318295.42' |
| 2074 | 2196803.74' | 6318361.47' |
| 2075 | 2196802.65' | 6318427.47' |
| 2076 | 2196851.00' | 6318527.99' |
| 2077 | 2196801.57' | 6318493.50' |
| 2078 | 2196799.37' | 6318625.60' |
| 2079 | 2196798.30' | 6318691.61' |
| 2101 | 2197009.76' | 6318639.77' |
| 2102 | 2196982.88' | 6318617.16' |
| 2103 | 2196924.14' | 6318635.77' |

| GRID COORDINATES (U.S. SURVEY FEET) | | |
|-------------------------------------|-------------|-------------|
| POINT | NORTHING | EASTING |
| 2104 | 2196923.41' | 6318679.38' |
| 2105 | 2196983.03' | 6318698.15' |

