


CORNER RECORD

DOCUMENT NO. CR-16-447

CITY OF Stockton, COUNTY OF San Joaquin, CALIFORNIA

Brief Legal Description: Northwest corner of Lot 358, Stonewood, Unit No. 6, 21-M&P-22

IN SECTION 9, TOWNSHIP 2 NORTH, RANGE 6 EAST, MOUNT DIABLO BASE AND MERIDIAN



CORNER TYPE

- Government Corner Control
 - Meander Property
 - Rancho Other
- Date of Survey 2016-05-19

COORDINATES (Optional)

- N. _____
- E. _____
- Zone _____ NAD27 NAD83
- NAD83 Epoch _____
- Elev. _____
- Vert. Datum: NGVD29 NAVD88
- Meas. Units: Metric Imperial

Corner: Left as Found Found and Tagged Established Reestablished Rebuilt

Identification and type of corner found: Evidence used to identify or procedure used to establish or reestablish the corner:

FOUND CENTERLINE MONUMENTS PER RECORD MAPS TO ESTABLISH RECORD POSITIONS. FOUND SCRIBED "+" AS A 6.00'
WITNESS CORNER ON THE NORTHERLY PROLONGATION OF THE EAST LINE OF LOT 358 AND THE WEST LINE OF LOT 357 AS
SHOWN ON (R1) AS NOTED ON SHEET 2. USED THIS TO REESTABLISH THE POSITION OF THE NORTHWEST CORNER OF LOT 358

A description of the physical condition of the monument as found and as set or reset: _____

SET A MAG NAIL WITH A BRASS TAG STAMPED LS 8366 AS A 6.00' WITNESS CORNER FOR THE NORTHWEST CORNER OF
LOT 358 PER (R1). SEE SHEET TWO FOR DETAILS.

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with the Land Surveyor's Act on NOVEMBER 4TH, 2016.

Signed [Signature] P.L.S. or R.C.E. No.: PLS 8366



COUNTY SURVEYOR'S STATEMENT

This Corner Record was received November 10, 2016 and examined and filed December 9, 2016.

Signed Warren D. Smith P.L.S. or R.C.E. No.: 4842

Title County Surveyor

County Surveyor's Comment _____



FOUND 3/4" IRON PIPE
TAGGED RCE 8189 IN
MONUMENT WELL (R1)

S0°40'00"W 260.00'

VALLEYOAK DRIVE

FOUND 3/4" IRON PIPE
TAGGED RCE 8189 IN
MONUMENT WELL (R2)

REFERENCES:

- (R1) STONEWOOD, UNIT NO 6;
21-M&P-22
- (R2) STONEWOOD, UNIT NO 5;
21-M&P-3

NOTE:

ALL DISTANCES SHOWN ARE
PER (R1) AND (R2) UNLESS
OTHERWISE NOTED.

OAKLEAF WAY

SUNNYOAK WAY

S89°16'33"E 1340.47'

30'

N0°43'27"E
24.00'

FOUND SCRIBED "+"
6.00' FROM LOT
CORNER, NO RECORD

LOT 358
(R1)

SET MAG NAIL AND
BRASS TAG STAMPED
LS 8366, FOR 6.00'
WITNESS CORNER

60.00'

65.00'

N0°43'27"E
24.00'

FOUND SCRIBED "+"
6.00' FROM LOT
CORNER, NO RECORD

N0°43'27"E
24.00'

295.00'

30'

STONEWOOD DRIVE

FOUND 3/4" IRON PIPE
TAGGED RCE 8189 IN
MONUMENT WELL (R1)

1"=100'

SCALE

