


# CORNER RECORD

Agency Index CR-17-269  
 Document Number \_\_\_\_\_

City of \_\_\_\_\_ County of San Joaquin, California  
 Brief Legal Description replacement monument for NGS BM F 473 - PID HS0432, Sec 24/T1N/R5E



**CORNER TYPE**

Government Corner  Control  
 Meander  Property  
 Rancho  Other

Date of Survey August 1, 2017

**COORDINATES (Optional)**

N. 2161070+/- E. 6309235+/-  
 Elevation 1.30(NAVD88), -1.13(NGVD29)  
 Units  Metric  U.S. Survey Foot  
 Horizontal Datum NAD83  
 Zone 3 Epoch Date N/A  
 Vertical Datum NAVD 88/NGVD29  
 Complies with Public Resources Code §§8801-8819  
 Complies with Public Resources Code §§8890-8902

PLS Act Ref.:  8765(d)  8771  8773  Other:  
 Corner/ Monument:  Left as found  Established  Rebuilt  Pre-Construction  
 Found and tagged  Reestablished  Referenced  Post-Construction

Narrative of corner identified and monument as found, set, reset, replaced, or removed:  
 See sheet #2 for description(s):

Benchmark F473 Reset 197? was destroyed during reconstruction of headwall in 2015+/-.  
 A new Brass cap was set in the new headwall on July 31, 2017 and new elevations established.

Brass Cap F473 set 1951.....EI= -1.083 (NGVD29), L21067, NGS rerun levels, pg 25 Of 54, 1967.  
 Brass Cap F473 Reset 197? .....EI= -0.87 (NGVD29) per Caltrans bench run SR970848, 1998

### SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with  
 the Professional Land Surveyors' Act on August 11, 2017  
 Signed [Signature] P.L.S. or R.C.E. No. LS 6406



### COUNTY SURVEYOR'S STATEMENT

This Corner Record was received August 16, 2017  
 and examined and filed September 8, 2017  
 Signed [Signature] P.L.S. or R.C.E. No. 4842  
 Title County Surveyor



County Surveyor's Comment

DISTRICT: 10 COUNTY: SJ ROUTE: 4 PM: 11.68 MON: MAYBECK 2017

DESCRIPTION: SET 2 1/4" BRASS NAIL STAMPED "CALIF DEPT OF TRANSPORTATION MAYBECK 2017" IN TOP OF HEADWALL OF IRRIGATION DITCH AT THE SOUTHEAST CORNER OF SJ 4 END MAYBECK ROAD.

POINT IS AT THE EAST END OF THE NORTH WALL, 16.0 FEET FROM THE POST OF A STOP SIGN, 32 FEET WEST OF THE CENTERLINE OF A PARALLEL DRAINAGE DITCH AND 42.7 FEET EAST OF THE PAINTED CENTERLINE OF MAYBECK ROAD.

SKETCH

