


# CORNER RECORD

Agency Index CR-17-370

Document Number \_\_\_\_\_

City of StocktonCounty of San Joaquin, CaliforniaBrief Legal Description Colonial West, Unit No. 5, Volume 19 of Maps & Plats, Page 84.

T 2 N., R. 6 E., M.D.B.&amp;M

## CORNER TYPE

Government Corner  Control   
 Meander  Property   
 Rancho  Other

Date of Survey September 22, 2017

## COORDINATES (Optional)

N. \_\_\_\_\_ E. \_\_\_\_\_

Elevation \_\_\_\_\_

Units Metric  U.S. Survey Foot Horizontal Datum NAD83Zone III Epoch Date 1991.35

Vertical Datum \_\_\_\_\_

 Complies with Public Resources Code §§8801-8819 Complies with Public Resources Code §§8890-8902

PLS Act Ref:  8765(d)  8771  8773  Other: \_\_\_\_\_  
 Corner/Monument:  Left as found  Established  Rebuilt  Pre-Construction  
 Found and tagged  Reestablished  Referenced  Post-Construction

Narrative of corner identified and monument as found, set, reset, replaced, or removed:

 See sheet #2 for description(s) :

Used conventional survey methods and CR 16-56 to reestablish the position of obliterated cut cross, as shown on page 2. Set cut cross with brass tag stamped L.S. 7051 in concrete. Also, found 3/4" iron pipes in wells, tagged "R.C.E. 15831", as shown on page 2.

## SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act on October 17, 2017.  
 Signed [Signature] P.L.S. or R.C.E. No. 7051



## COUNTY SURVEYOR'S STATEMENT

This Corner Record was received November 29, 2017  
 and examined and filed December 28, 2017.  
 Signed Warren D. Smith P.L.S. or R.C.E. No. 4842  
 Title County Surveyor



County Surveyor's Comment

**STATEMENT OF PURPOSE:**

THE PURPOSE OF THIS SURVEY IS TO RECORD AND REESTABLISH THE LOCATION OF MONUMENTS ORIGINALLY SHOWN ON CR 16-56 DISTURBED AFTER THE CONSTRUCTION OF UNDERGROUND IMPROVEMENTS. THE PURPOSE OF THIS SURVEY IS NOT TO MAKE PROPERTY LINE DETERMINATIONS. LOT LINES SHOWN HEREON ARE FOR GENERAL LOCATION AND INFORMATIONAL PURPOSES ONLY.

**DATUM STATEMENT:**

COORDINATES SHOWN HEREON ARE GRID AND ARE BASED ON CITY OF STOCKTON MONUMENTS 4N-6 AND 4N-10, CALIFORNIA COORDINATE SYSTEM (CCS83), ZONE III, 1983 NAD, (1991.35 EPOCH STOCKTON & SAN JOAQUIN COUNTY GPS ADJUSTMENT) AND SHOWN ON RECORD OF SURVEY BOOK 33 OF SURVEYS, PAGE 20. THE PROJECT SPECIFIC COMBINED SCALE FACTOR IS 0.99994060.

**LEGEND:**

- ⊗ INDICATES SET BRASS TAG STAMPED L.S. 7051.
- INDICATES FOUND 3/4" IRON PIPES IN WELL TAGGED R.C.E. 15831

GRID COORDINATES (U.S. SURVEY FEET)		
POINT	NORTHING	EASTING
2007	2197711.78'	6318940.54'
2008	2197752.50'	6319021.48'
2009	2197820.28'	6318993.11'
2010	2197802.14'	6319280.74'
2198	2197753.08'	6319099.20'

