


# CORNER RECORD

Agency Index CR-17-372  
Document Number \_\_\_\_\_

City of Stockton County of San Joaquin, California  
Brief Legal Description Colonial West, Unit No. 5, Volume 19 of Maps & Plats, Page 84.



T 2 N., R. 6 E., M.D.B.&M

### CORNER TYPE

- Government Corner  Control
- Meander  Property
- Rancho  Other

Date of Survey September 22, 2017

### COORDINATES (Optional)

- N. \_\_\_\_\_ E. \_\_\_\_\_
- Elevation \_\_\_\_\_
- Units Metric  U.S. Survey Foot
- Horizontal Datum NAD83
- Zone III Epoch Date 1991.35
- Vertical Datum \_\_\_\_\_
- Complies with Public Resources Code §§8801-8819
- Complies with Public Resources Code §§8890-8902

PLS Act Ref:  8765(d)  8771  8773  Other: \_\_\_\_\_

Corner/Monument:  Left as found  Established  Rebuilt  Pre-Construction

Found and tagged  Reestablished  Referenced  Post-Construction

Narrative of corner identified and monument as found, set, reset, replaced, or removed:

See sheet #2 for description(s) :

Used conventional survey methods and CR 16-58 to reestablish the position of obliterated cut cross, as shown on page 2. Set cut cross with brass tags stamped L.S. 7051 in concrete. Also, found 3/4" iron pipes in wells, tagged "R.C.E. 15831", as shown on page 2.

### SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with  
the Professional Land Surveyors' Act on October 17, 2017.

Signed [Signature] P.L.S. or R.C.E. No. 7051



### COUNTY SURVEYOR'S STATEMENT

This Corner Record was received November 29, 2017  
and examined and filed December 28, 2017.

Signed [Signature] P.L.S. or R.C.E. No. 4842

Title County Surveyor



County Surveyor's Comment \_\_\_\_\_

**STATEMENT OF PURPOSE:**

THE PURPOSE OF THIS SURVEY IS TO RECORD AND REESTABLISH THE LOCATION OF MONUMENTS ORIGINALLY SHOWN ON CR 16-58 DISTURBED AFTER THE CONSTRUCTION OF UNDERGROUND IMPROVEMENTS. THE PURPOSE OF THIS SURVEY IS NOT TO MAKE PROPERTY LINE DETERMINATIONS. LOT LINES SHOWN HEREON ARE FOR GENERAL LOCATION AND INFORMATIONAL PURPOSES ONLY.

**DATUM STATEMENT:**

COORDINATES SHOWN HEREON ARE GRID AND ARE BASED ON CITY OF STOCKTON MONUMENTS 4N-6 AND 4N-10, CALIFORNIA COORDINATE SYSTEM (CCS83), ZONE III, 1983 NAD, (1991.35 EPOCH STOCKTON & SAN JOAQUIN COUNTY GPS ADJUSTMENT) AND SHOWN ON RECORD OF SURVEY BOOK 33 OF SURVEYS, PAGE 20. THE PROJECT SPECIFIC COMBINED SCALE FACTOR IS 0.99994060.

**LEGEND:**

- ⊙ INDICATES SET BRASS TAG STAMPED L.S. 7051.
- INDICATES FOUND 3/4" IRON PIPES IN WELL TAGGED R.C.E. 15831

GRID COORDINATES (U.S. SURVEY FEET)		
POINT	NORTHING	EASTING
2016	2197212.35'	6319153.32'
2017	2197240.40'	6319302.73'
2052	2197116.31'	6319168.39'
2174	2197307.87'	6319105.32'
2175	2197242.63'	6319121.71'

