

CORNER RECORD

Agency Index CR-18-103
 Document Number _____

City of _____ County of San Joaquin, California
 Brief Legal Description Section Corner 12 & 13, T1N, R7E and 7 & 18, T1N, R8E, MDM

CORNER TYPE		COORDINATES (Optional)	
	<input checked="" type="checkbox"/> Government Corner	<input type="checkbox"/> Control	N. _____ E. _____
	<input type="checkbox"/> Meander	<input type="checkbox"/> Property	Elevation _____
	<input type="checkbox"/> Rancho	<input type="checkbox"/> Other	Units <input type="checkbox"/> Metric <input type="checkbox"/> U.S. Survey Foot
	Date of Survey <u>February 5, 2018</u>		Horizontal Datum _____
		Zone _____ Epoch Date _____	Vertical Datum _____
		<input type="checkbox"/> Complies with Public Resources Code §§8801-8819	
		<input type="checkbox"/> Complies with Public Resources Code §§8890-8902	

PLS Act Ref.:	<input type="checkbox"/> 8765(d)	<input type="checkbox"/> 8771	<input type="checkbox"/> 8773	<input type="checkbox"/> Other:
Corner/Monument:	<input type="checkbox"/> Left as found	<input type="checkbox"/> Established	<input type="checkbox"/> Rebuilt	<input type="checkbox"/> Pre-Construction
	<input type="checkbox"/> Found and tagged	<input type="checkbox"/> Reestablished	<input checked="" type="checkbox"/> Referenced	<input type="checkbox"/> Post-Construction

Narrative of corner identified and monument as found, set, reset, replaced, or removed:
 See sheet #2 for description(s):
 Found shaft of railroad spike in monument well. Corner Records 05-18 and 08-76 show differing dimensions to the same ties in the southwest and southeast quadrants. We re-measured those ties and added ties in the northwest and northeast quadrants. See page 2 for details.

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act on February 20, 2018.
 Signed [Signature] P.L.S. or R.C.E. No. LS6406



COUNTY SURVEYOR'S STATEMENT

This Corner Record was received May 8, 2018 and examined and filed May 8, 2018.
 Signed [Signature] P.L.S. or R.C.E. No. 8657
 Title Acting County Surveyor
 County Surveyor's Comment _____



D.D. Sheet Nos. 37 + 38

DISTRICT: 10 COUNTY: SJ ROUTE: 4 PM: 24.87 MON: MON 200

DESCRIPTION: Found shaft of railroad spike in poor condition in monument well, down 0.8 ft. Point is in the intersection of SJ 4 and Jack Tone Road. Monument well lid is missing and the well has been filled with dirt and asphalt. Set concrete nails with brass 'Caltrans Tie Pt' tags as swing ties at 2.0 ft east and north, and set 2"x2" hub with tack at surface.

Found references per CR 05-18: a 3.5" brass USC&GS "Z959 1963" disk in headwall 56.39 ft southeast, and scribed cross in headwall 55.54 ft southwest. Set PK nails with brass "Caltrans" washers in headwalls 53.82 ft northeast and 52.64 ft northwest.

