


CORNER RECORD

Agency Index CR-19-16
Document Number _____

City of Manteca County of San Joaquin, California
Brief Legal Description Portion of East 1/2 of the SE. 1/4 of Section 34, T. 1 S., R. 7 E., M.D.M.



CORNER TYPE

- Government Corner
- Meander
- Rancho
- Control
- Property
- Other

Date of Survey December 21, 2018

COORDINATES (Optional)

N. _____ E. _____
 Elevation 49.23
 Units Metric U.S. Survey Foot
 Horizontal Datum _____
 Zone _____ Epoch Date _____
 Vertical Datum NAVD88
 Complies with Public Resources Code §§8801-8819
 Complies with Public Resources Code §§8890-8902

PLS Act Ref.: 8765(d) 8771 8773 Other:
 Corner/Monument: Left as found Established Rebuilt Pre-Construction
 Found and tagged Reestablished Referenced Post-Construction

Narrative of corner identified and monument as found, set, reset, replaced, or removed:
 See sheet #2 for description(s):

City of Manteca Benchmark No. 55 (NGS C968) is located in an area that it may be destroyed by the proposed re-construction of the return at the Northeast corner of Yosemite Ave. (State Route 120) and Vasconcellos Ave. A new 2" diameter brass disk has been placed at the North end of the Northwest Return as shown on page 2 of 2 of this Corner Record.

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with
 the Professional Land Surveyors' Act on January 29, 2019
 Signed [Signature] P.L.S. or R.C.E. No. 7126




COUNTY SURVEYOR'S STATEMENT

This Corner Record was received January 31, 2019
 and examined and filed February 13, 2019
 Signed [Signature] P.L.S. or R.C.E. No. 8657
 Title Acting County Surveyor
 County Surveyor's Comment _____



SCALE: 1"=20'



DIFFERENTIAL LEVELING

STA	+Ø	H.I.	-Ø	ELEV
EX.BM (C958)	3.76	53.33		49.57
NEW BM#55			4.10	49.23

CITY OF MANTECA BENCHMARK
 NO. 55, BEING A 2" BRASS DISK,
 STAMPED NO. 55, DRILLED AND
 EPOXIED INTO THE TOP OF CURB
 ELEV. 49.23 (NAVD88) REPLACING BM.
 NO. 55

VASCONCELLOS AVENUE

CITY OF MANTECA BENCHMARK
 NO. 55, BEING A 3" BRASS DISK,
 STAMPED NGS C958, RESET 1993
 ELEV. 49.57 (NAVD88) MAY BE
 DISTURBED DURING SITE RE-CONST.
 OF THE RETURN. SHOWN AS PT. 103
 IN BOOK 33 OF SURVEYS AT PAGE 133,
 SAN JOAQUIN COUNTY RECORDS



YOSEMITE AVENUE (STATE RTE. 120)