

CORNER RECORD

Agency Index CR-19-43
Document Number _____

City of _____ County of SAN JOAQUIN, California
Brief Legal Description SJCO BM - WEST SIDE OF AUSTIN RD, 640' NORTH OF GRAVES RD



CORNER TYPE

- Government Corner
- Meander
- Rancho
- Control
- Property
- Other

Date of Survey March 1, 2019

COORDINATES (Optional)

- N. _____ E. _____
Elevation _____
Units Metric U.S. Survey Foot
Horizontal Datum _____
Zone _____ Epoch Date _____
Vertical Datum _____
 Complies with Public Resources Code §§8801-8819
 Complies with Public Resources Code §§8890-8902

- PLS Act Ref.: 8765(d) 8771 8773 Other:
Corner/Monument: Left as found Established Rebuilt Pre-Construction
 Found and tagged Reestablished Referenced Post-Construction

Narrative of corner identified and monument as found, set, reset, replaced, or removed:
 See sheet #2 for description(s):

THE PURPOSE OF THIS CORNER RECORD IS TO REESTABLISH SJCO VERTICAL BENCHMARK O-36.2 WHICH WAS DESTROYED DURING CONSTRUCTION.

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act on APRIL 10, 2019
Signed Eric Finley P.L.S. or R.C.E. No. 9228



COUNTY SURVEYOR'S STATEMENT

This Corner Record was received April 17, 2019
and examined and filed May 2, 2019
Signed James E. Hart P.L.S. or R.C.E. No. 8657
Title County Surveyor
County Surveyor's Comment _____





NO SCALE

NE 1/4 OF SECTION 10
T. 2 S., R. 7 E., MDM

NW 1/4 OF SECTION 11
T. 2 S., R. 7 E., MDM

SET CONCRETE MONUMENT
WITH 3.5" BRASS DISK
MARKED "RESET O-36.2"
RESULTANT ELEVATION = 46.12'



AUSTIN ROAD

± 640'

FND CONCRETE MONUMENT
WITH 3.5" BRASS DISK
MARKED "MN-36.3"

GRAVES ROAD

± 8,250'



NOTES:

1. THE ORIGINAL MONUMENT WAS ON VERTICAL DATUM NGVD 29
2. THE MONUMENT WAS RESET USING A DIGITAL LEVEL AND CLOSED LOOP FROM BENCHMARK "MN-36.3" WHICH ACCORDING TO SAN JOAQUIN COUNTY'S BENCHMARK DATABASE HAS AN ELEVATION OF 55.29' ON VERTICAL DATUM NGVD 29