

# CORNER RECORD


Agency Index: CR-21-209

Document Number: \_\_\_\_\_

City of LATHROP

County of SAN JOAQUIN, California

Brief Legal Description MONUMENTS AT THE INTERSECTION OF LOUISE AVENUE AND WARFIELD ROAD IN MONUMENT WELLS DUE EAST OF SECTION CORNER.



### CORNER TYPE

- Government Corner     Control  
 Meander                     Property  
 Rancho                         Other

Date of Survey 06-16-2021

### COORDINATES (Optional)

N. \_\_\_\_\_ E. \_\_\_\_\_  
 Elevation \_\_\_\_\_  
 Units     Metric     U.S. Survey Foot  
 Horizontal Datum \_\_\_\_\_  
 Zone \_\_\_\_\_ Epoch Date \_\_\_\_\_  
 Vertical Datum \_\_\_\_\_  
 Complies with Public Resources Code SS8801-8819  
 Complies with Public Resources Code SS8890-8902

PLS Act Ref:     8765(d)                     8771                     8773                     Other:

Corner/ Monument:     Left as found                     Established                     Rebuilt                     Pre-Construction  
                                    Found and Tagged                 Reestablished                 Referenced                     Post-Construction

Narrative of corner identified and monument as found, set, reset, replaced, or removed:

See sheet #2 for description(s):

FOUND THREE (3) CONCRETE NAILS WITH BRASS TAG STAMPED "L.S. 6953" AS SHOWN ON CORNER RECORD NO. 21-015, S.J.C.S.R. SET TWO (2) 2 1/2" BRASS DISKS STAMPED "3-2021 L.S. 6953" IN MONUMENT WELLS AT THE INTERSECTION OF LOUISE AVENUE AND WARFIELD ROAD, ALL AS SHOWN ON PAGE 2.

### SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with the Land Surveyors' Act on JUNE 28, 2021,



Signed [Signature] P.L.S. or R.C.E. Number 6953

### COUNTY SURVEYOR'S STATEMENT

This Corner Record was received October 14, 2021 and examined and filed November 4, 2021

Signed [Signature] P.L.S. or R.C.E. No: 8657

Title County Surveyor



County Surveyor's Comment \_\_\_\_\_

REFERENCES:

(R1) CR-21-015, S.J.C.S.R.

LEGEND:

- FOUND CONCRETE NAILS W/ BRASS TAG STAMPED "L.S. 6953"
- ⊗ SET 2 1/2" BRASS DISK STAMPED "3-2021 L.S. 6953"
- S.J.C.S.R. DENOTES SAN JOAQUIN COUNTY SURVEYORS RECORDS
- (M) MEASURED DISTANCE. ALL DISTANCES ARE MEASURED UNLESS OTHERWISE NOTED

<i>⊗ AND DISTANCE TABLE</i>		
<i>BS-@-FS</i>	<i>⊗</i>	<i>FS DISTANCE</i>
<i>B-A-B</i>	<i>00°00'00"</i>	<i>287.66'(M)(R1)</i>
<i>B-A-C</i>	<i>03°16'40"</i>	<i>29.92'(M)(R1)</i>
<i>B-A-D</i>	<i>00°00'00"</i>	<i>192.17'(M)(R1)</i>
<i>B-A-E</i>	<i>00°00'00"</i>	<i>97.18'(M)(R1)</i>

