


# CORNER RECORD

Agency Index CR-22-182  
 Document Number \_\_\_\_\_

City of Stockton, County of San Joaquin, California

Brief Legal Description **A point on or near the centerline of North El Dorado Street lying approximately 200 feet southerly of the concrete bridge over Mosher Slough. Position undetermined.**

| CORNER TYPE                                |                                   | COORDINATES (Optional)   |   |
|--|-----------------------------------|--|---|
| <input type="checkbox"/> Government Corner | <input type="checkbox"/> Control  | N. _____ N/A _____   | E. _____ N/A _____                              |
| <input type="checkbox"/> Meander           | <input type="checkbox"/> Property | Elevation _____ N/A _____  |   |
| <input type="checkbox"/> Rancho            | <input type="checkbox"/> Other    | Units <input type="checkbox"/> Metric <input type="checkbox"/> U.S. Survey Foot <input type="checkbox"/> |   |
| Date of Survey <u>05/22/2022</u>           |                                   | Horizontal Datum _____ N/A _____   | Zone _____ N/A _____ Epoch Date _____ N/A _____ |
|  |                                   | Vertical Datum _____   |   |
|  |                                   | <input type="checkbox"/> Complies with Public Resources Code §§8801-8819                                 |   |
|  |                                   | <input type="checkbox"/> Complies with Public Resources Code §§8890-8902                                 |   |



PLS Act Ref.:  8765(d)  8771  8773  Other

Corner / Monument:  Left as found  Established  Rebuilt  Pre-Construction  
 Found and tagged  Reestablished  Referenced  Post-Construction

Narrative of corner identified and monument as found, set, reset, replaced, or removed:  
 See sheet #2 for description(s):

Found MAG nail and tin (point #3) in faded paint flight cross, no tag, no apparent record, position undetermined. This MAG nail does not appear to mark a record location nor does it appear to be shown on a record map and was likely set as flight control. Set four (4) 1-1/4" brass discs stamped "SURVEY POINT" being drilled and then driven into the top of a concrete curb as reference points. See Page 2 of 2 for a depiction of this survey. Angles and distances established utilizing a total station.

### SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act on June 30, 2022

Signed Robert W. Snow 07-01-2022 P.L.S. or R.C.E. No. 8813



### COUNTY SURVEYOR'S STATEMENT

This Corner Record was received July 8, 2022  
 and examined and filed July 22, 2022

Signed James E. Hart P.L.S. or R.C.E. No. 8657  
 Title County Surveyor



County Surveyor's Comment

DATE: 06/30/2022  
PAGE: 2 OF 6

PROJECT: ROAD DIET ON N. EL DORADO STREET, TURN AND BIKE LANES  
FEDERAL PROJECT NO. HSIPL-5008(162) AND CITY PROJECT NO. WT17019  
REFERENCE NOTES FOR FOUND MONUMENTS  
CITY OF STOCKTON, COUNTY OF SAN JOAQUIN

FIELD CREW:  
R. SNOW & A. MAWLAAE

| FROM - TO | HZ. ANGLE        | HZ. DISTANCE |
|-----------|------------------|--------------|
| 103-104   | 00°00'00"        | 225.02'      |
| 103-3     | ∠ R = 09°03'53"  | 204.64'      |
| 103-105   | ∠ R = 15°18'06"  | 245.47'      |
| 103-106   | ∠ R = 20°36'47"  | 184.20'      |
| 103-107   | ∠ R = 149°47'10" | 129.34'      |
| 103-4     | ∠ R = 154°43'53" | 175.50'      |
| 103-108   | ∠ R = 164°36'53" | 246.66'      |
| 103-5     | ∠ R = 172°07'54" | 260.77'      |
| 103-109   | ∠ R = 172°30'14" | 503.38'      |
| 103-6     | ∠ R = 181°40'53" | 305.06'      |
| 103-110   | ∠ R = 179°42'34" | 189.28'      |

- #103, #104, #105, #106, #107, #108, #109, & #110 - SET 1-1/4" BRASS DISC AS REFERENCE POINT, STAMPED "SURVEY POINT", IN TOP OF CURB
- #3 - FOUND MAG NAIL AND SHINER IN PAINTED FLIGHT X.
- #4 - FOUND 3/4" REBAR WITH BRASS TAG STAMPED "RCE 15831" LOCATED IN A MONUMENT BOX ON THE CENTERLINE OF ORLEANS COURT AT THE WEST LINE OF NORTH EL DORADO STREET PER 21 M 63
- #5 - FOUND NAIL AND WASHER, NO APPARENT STAMPING, NO APPARENT RECORD, LYING WITHIN NORTH EL DORADO STREET, JUST SOUTH OF MARTINIQUE COURT
- #6 - FOUND 3/4" REBAR WITH BRASS TAG STAMPED "RCE 15831", LOCATED IN A MONUMENT BOX ON THE CENTERLINE OF MARTINIQUE COURT AT THE EAST LINE OF NORTH EL DORADO STREET PER 21 M 63

- LEGEND:**
- FOUND NAIL AND WASHER, NO APPARENT STAMPING, NO APPARENT RECORD, POSITION UNDETERMINED
  - SET 1-1/4" BRASS DISC AS REFERENCE POINT, STAMPED "SURVEY POINT"
  - ◆ FOUND 3/4" REBAR WITH BRASS TAG STAMPED "RCE 15831" PER 21 M 63
  - ◆ FOUND MAG NAIL AND SHINER NEAR CENTER OF STREET, IN PAINTED FLIGHT X; NO APPARENT RECORD, POSITION UNDETERMINED
  - BACK OF WALK
  - EP EDGE OF PAVEMENT
  - M MAPS AND PLATS, S.J.C.R.



S.J.C.R. SAN JOAQUIN COUNTY RECORDS

