


# CORNER RECORD

Agency Index CR-22-184

Document Number \_\_\_\_\_

City of Stockton, County of San Joaquin, California

Brief Legal Description **A point on or near the centerline of North El Dorado Street just south of Martinique Court. Position undetermined.**



### CORNER TYPE

- Government Corner  Control
- Meander  Property
- Rancho  Other

Date of Survey 05/22/2022

### COORDINATES (Optional)

N. N/A E. N/A

Elevation N/A

Units  Metric  U.S. Survey Foot

Horizontal Datum N/A

Zone N/A Epoch Date N/A

Vertical Datum \_\_\_\_\_

- Complies with Public Resources Code §§8801-8819
- Complies with Public Resources Code §§8890-8902

PLS Act Ref.:  8765(d)  8771  8773  Other

Corner / Monument:  Left as found  Established  Rebuilt  Pre-Construction  
 Found and tagged  Reestablished  Referenced  Post-Construction

Narrative of corner identified and monument as found, set, reset, replaced, or removed:

See sheet #2 for description(s):

Found nail and washer, no visible stamp (point #5), no apparent record, position undetermined. This nail and washer does not appear to mark a record location nor does it appear to be shown on a record map. Set four (4) 1-1/4" brass discs stamped "SURVEY POINT" being drilled and then driven into the top of a concrete curb as reference points. See Page 2 of 2 for a depiction of this survey. Angles and distances established utilizing a total station.

### SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act on June 30, 2022

Signed Robert W. Snow 07-01-2022 P.L.S. or R.C.E. No. 8813



### COUNTY SURVEYOR'S STATEMENT

This Corner Record was received July 8, 2022  
and examined and filed July 22, 2022

Signed James E. Hart P.L.S. or R.C.E. No. 8657  
James E. Hart

Title County Surveyor

County Surveyor's Comment



DATE: 06/30/2022

PAGE: 2 OF 6

PROJECT: ROAD DIET ON N. EL DORADO STREET, TURN AND BIKE LANES

FEDERAL PROJECT NO. HSIPL-5008(162) AND CITY PROJECT NO. WT17019

REFERENCE NOTES FOR FOUND MONUMENTS

CITY OF STOCKTON, COUNTY OF SAN JOAQUIN

FIELD CREW:

R. SNOW & A. MAWLAAE

FROM - TO	HZ. ANGLE	HZ. DISTANCE
103-104	00°00'00"	225.02'
103-3	∠ R = 09°03'53"	204.64'
103-105	∠ R = 15°18'06"	245.47'
103-106	∠ R = 20°36'47"	184.20'
103-107	∠ R = 149°47'10"	129.34'
103-4	∠ R = 154°43'53"	175.50'
103-108	∠ R = 164°36'53"	246.66'
103-5	∠ R = 172°07'54"	260.77'
103-109	∠ R = 172°30'14"	503.38'
103-6	∠ R = 181°40'53"	305.06'
103-110	∠ R = 179°42'34"	189.28'

- #103, #104, #105, #106, #107, #108, #109, & #110 - SET 1-1/4" BRASS DISC AS REFERENCE POINT, STAMPED "SURVEY POINT", IN TOP OF CURB
- #3 - FOUND MAG NAIL AND SHINER IN PAINTED FLIGHT X.
- #4 - FOUND 3/4" REBAR WITH BRASS TAG STAMPED "RCE 15831" LOCATED IN A MONUMENT BOX ON THE CENTERLINE OF ORLEANS COURT AT THE WEST LINE OF NORTH EL DORADO STREET PER 21 M 63
- #5 - FOUND NAIL AND WASHER, NO APPARENT STAMPING, NO APPARENT RECORD, LYING WITHIN NORTH EL DORADO STREET, JUST SOUTH OF MARTINIQUE COURT
- #6 - FOUND 3/4" REBAR WITH BRASS TAG STAMPED "RCE 15831", LOCATED IN A MONUMENT BOX ON THE CENTERLINE OF MARTINIQUE COURT AT THE EAST LINE OF NORTH EL DORADO STREET PER 21 M 63

**LEGEND:**

- FOUND NAIL AND WASHER, NO APPARENT STAMPING, NO APPARENT RECORD, POSITION UNDETERMINED
  - SET 1-1/4" BRASS DISC AS REFERENCE POINT, STAMPED "SURVEY POINT"
  - FOUND 3/4" REBAR WITH BRASS TAG STAMPED "RCE 15831" PER 21 M 63
  - ◆ FOUND MAG NAIL AND SHINER NEAR CENTER OF STREET, IN PAINTED FLIGHT X, NO APPARENT RECORD, POSITION UNDETERMINED
  - BOW BACK OF WALK
  - EP EDGE OF PAVEMENT
  - M MAPS AND PLATS, S.J.C.R.
- S.J.C.R. SAN JOAQUIN COUNTY RECORDS

