

CORNER RECORD

Agency Index CR-22-186

Document Number _____

City of Stockton, County of San Joaquin, California

Brief Legal Description **The centerline of Normandy Court at the west line of N. El Dorado Street per 21 M 63.**

CORNER TYPE		COORDINATES (Optional)	
<input type="checkbox"/>	Government Corner	<input type="checkbox"/>	Control
<input type="checkbox"/>	Meander	<input type="checkbox"/>	Property
<input type="checkbox"/>	Rancho	<input type="checkbox"/>	Other
Date of Survey <u>05/22/2022</u>		Vertical Datum _____	
		<input type="checkbox"/> Complies with Public Resources Code §§8801-8819	
		<input type="checkbox"/> Complies with Public Resources Code §§8890-8902	

PLS Act Ref.: 8765(d) 8771 8773 Other

Corner / Monument: Left as found Established Rebuilt Pre-Construction
 Found and tagged Reestablished Referenced Post-Construction

Narrative of corner identified and monument as found, set, reset, replaced, or removed:
 See sheet #2 for description(s):

Found 3/4" rebar with brass tag stamped "RCE 15831 (point #7) located in a monument box on the centerline of Normandy Court at the west line of North El Dorado Street per 21 M 63. Set three (3) 1-1/4" brass discs stamped "SURVEY POINT" being drilled and then driven into the top of a concrete curb as reference points. See Page 2 of 2 for a depiction of this survey. Angles and distances established utilizing a total station.

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act on June 30, 2022

Signed Robert W. Snow P.L.S. or R.C.E. No. 8813



COUNTY SURVEYOR'S STATEMENT

This Corner Record was received July 8, 2022
 and examined and filed July 22, 2022.

Signed James E. Hart P.L.S. or R.C.E. No. 8657

Title County Surveyor



County Surveyor's Comment

DATE: 06/30/2022

PAGE: 3 OF 6

FROM - TO	HZ. ANGLE	HZ. DISTANCE
109-103	00°00'00"	503.38'
109-5	∠ R = 00°23'59"	242.60'
109-111	∠ R = 07°27'21"	139.50'
109-7	∠ R = 14°00'41"	84.20'
109-112	∠ R = 191°21'15"	321.79'
109-8	∠ R = 194°14'46"	227.66'
109-9	∠ R = 210°31'50"	280.96'
109-113	∠ R = 338°17'07"	132.30'
109-6	∠ R = 346°28'04"	207.96'

PROJECT: ROAD DIET ON N. EL DORADO STREET, TURN AND BIKE LANES

FEDERAL PROJECT NO. HSIPL-5008(162) AND CITY PROJECT NO. WT17019

REFERENCE NOTES FOR FOUND MONUMENTS

FIELD CREW:

CITY OF STOCKTON, COUNTY OF SAN JOAQUIN

R. SNOW & A. MAWLAAEE

- #103, #109, #111, #112, & #113 - SET 1-1/4" BRASS DISC AS REFERENCE POINT, STAMPED "SURVEY POINT", IN TOP OF CURB
- #5 - FOUND NAIL AND WASHER, NO APPARENT STAMPING, NO APPARENT RECORD, LYING WITHIN NORTH EL DORADO STREET, JUST SOUTH OF MARTINIQUE COURT
- #6 & #7 - FOUND 3/4" REBAR WITH BRASS TAG STAMPED "RCE 15831", LOCATED IN A MONUMENT BOX ON THE CENTERLINE OF MARTINIQUE COURT AND NORMANDY COURT AT THE EAST AND WEST LINE OF NORTH EL DORADO STREET PER 21 M 63
- #8 & #9 - FOUND 3/4" IRON PIN WITH BRASS TAG STAMPED " RCE 8189" PER 20 M 27

LEGEND:

- FOUND NAIL AND WASHER, NO APPARENT STAMPING, NO APPARENT RECORD, POSITION UNDETERMINED
- SET 1-1/4" BRASS DISC AS REFERENCE POINT, STAMPED "SURVEY POINT", IN TOP OF CURB
- ⊙ FOUND 3/4" REBAR IN MONUMENT BOX PER 21 M 63 & 20 M 27
- SNF SEARCH NOTHING FOUND
- () RECORD DISTANCE
- BOW BACK OF WALK
- EP EDGE OF PAVEMENT
- M MAPS & PLATS, SAN JOAQUIN COUNTY RECORDS

