


CORNER RECORD

Agency Index CR-22-190
 Document Number _____

City of Stockton, County of San Joaquin, California

Brief Legal Description **The centerline of North El Dorado Street lying 118.69 feet (measured distance) northerly of the centerline intersection of N. El Dorado Street with Ponce De Leon Avenue per 18 M 23.**



CORNER TYPE

Government Corner Control
 Meander Property
 Rancho Other
 Date of Survey 05/22/2022

COORDINATES (Optional)

N. _____ N/A _____ E. _____ N/A _____
 Elevation _____ N/A _____
 Units Metric U.S. Survey Foot
 Horizontal Datum _____ N/A _____
 Zone _____ N/A _____ Epoch Date _____ N/A _____
 Vertical Datum _____
 Complies with Public Resources Code §§8801-8819
 Complies with Public Resources Code §§8890-8902

PLS Act Ref.: 8765(d) 8771 8773 Other
 Corner / Monument: Left as found Established Rebuilt Pre-Construction
 Found and tagged Reestablished Referenced Post-Construction

Narrative of corner identified and monument as found, set, reset, replaced, or removed:
 See sheet #2 for description(s):

Found 3/4" iron pin with brass tag stamped "RCE 8189" (point #11) located in a monument box on the centerline of North El Dorado Street lying 118.69 feet (measured distance) northerly of the centerline intersection of North El Dorado Street with Ponce De Leon Avenue per 18 M 23. Set three (3) 1-1/4" brass discs stamped "SURVEY POINT" being drilled and then driven into the top of a concrete curb as reference points. See Page 2 of 2 for a depiction of this survey. Angles and distances established utilizing a total station.

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act on June 30, 2022

Signed *Robert W. Snow* 07-01-2022 P.L.S. or R.C.E. No. 8813
 Robert W. Snow



COUNTY SURVEYOR'S STATEMENT

This Corner Record was received July 8, 2022
 and examined and filed July 22, 2022

Signed *James E. Hart* P.L.S. or R.C.E. No. 8657
 James E. Hart
 Title County Surveyor



County Surveyor's Comment

DATE: 06/30/2022

PAGE: 4 OF 6

FROM - TO	HZ. ANGLE	HZ. DISTANCE
112-109	00°00'00"	321.79'
112-10	∠ R = 13°56'45"	48.56'
112-114	∠ R = 36°50'05"	71.53'
112-11	∠ R = 104°58'10"	43.88'
112-12	∠ R = 137°55'52"	131.58'
112-115	∠ R = 338°25'17"	139.86'
112-8	∠ R = 353°04'33"	95.12'

PROJECT: ROAD DIET ON N. EL DORADO STREET, TURN AND BIKE LANES

FEDERAL PROJECT NO. HSIPL-5008(162) AND CITY PROJECT NO. WT17019

REFERENCE NOTES FOR FOUND MONUMENTS

FIELD CREW:

CITY OF STOCKTON, COUNTY OF SAN JOAQUIN

R. SNOW & A. MAWLAAE

#109, #112, #114, & #115 - SET 1-1/4" BRASS DISC AS REFERENCE POINT, STAMPED "SURVEY POINT", IN TOP OF CURB

#12 - FOUND NAIL AND WASHER, NO APPARENT STAMPING, NO APPARENT RECORD, LYING WITHIN NORTH EL DORADO STREET, JUST NORTH OF PONCE DE LEON AVENUE

#8, #10 & #11 - FOUND 3/4" REBAR WITH BRASS TAG STAMPED "RCE 15831", LOCATED IN A MONUMENT BOX ON THE CENTERLINE OF EL DORADO STREET PER 20 M 27

- LEGEND:**
- ◆ FOUND MAG NAIL AND SHINER NEAR CENTER OF STREET, NO APPARENT RECORD, POSITION UNDETERMINED
 - FOUND 3/4" REBAR IN MONUMENT BOX PER 21 M 63 & 20 M 27
 - SET 1-1/4" BRASS DISC AS REFERENCE POINT, STAMPED "SURVEY POINT", IN TOP OF CURB
 - SNF SEARCH NOTHING FOUND
 - () RECORD DISTANCE
 - BOW BACK OF WALK
 - EP EDGE OF PAVEMENT
 - M MAPS & PLATS, SAN JOAQUIN COUNTY RECORDS

