

CORNER RECORD

Agency Index CR-22-196
 Document Number _____

City of Stockton, County of San Joaquin, California

Brief Legal Description **Three (3) positions on or near the centerline of North El Dorado Street lying northerly of Morada Lane as shown on Corner Record CR-21-229.**

CORNER TYPE		COORDINATES (Optional)	
<input type="checkbox"/>	Government Corner	<input type="checkbox"/>	Control
<input type="checkbox"/>	Meander	<input type="checkbox"/>	Property
<input type="checkbox"/>	Rancho	<input type="checkbox"/>	Other
Date of Survey <u>05/22/2022</u>		Vertical Datum _____	
		<input type="checkbox"/> Complies with Public Resources Code §§8801-8819 <input type="checkbox"/> Complies with Public Resources Code §§8890-8902	

PLS Act Ref.: 8765(d) 8771 8773 Other

Corner / Monument: Left as found Established Rebuilt Pre-Construction
 Found and tagged Reestablished Referenced Post-Construction

Narrative of corner identified and monument as found, set, reset, replaced, or removed:
 See sheet #2 for description(s):

Found three (3) MAG nails and washers stamped "LS 6953" (points #17, #18, & #19) on or near the centerline of North El Dorado Street lying northerly of Morada Lane, as shown on Corner Record CR-21-229. Set three (3) 1-1/4" brass discs stamped "SURVEY POINT" being drilled and then driven into the top of a concrete curb as reference points. See Page 2 of 2 for a depiction of this survey. Angles and distances established utilizing a total station.

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act on June 30, 2022

Signed Robert W. Snow P.L.S. or R.C.E. No. 8813



COUNTY SURVEYOR'S STATEMENT

This Corner Record was received July 8, 2022
 and examined and filed July 22, 2022

Signed James E. Hart P.L.S. or R.C.E. No. 8657
 Title County Surveyor



County Surveyor's Comment

DATE: 06/30/2022

PAGE: 6 OF 6

PROJECT: ROAD DIET ON N. EL DORADO STREET, TURN AND BIKE LANES

FEDERAL PROJECT NO. HSIPL-5008(162) AND CITY PROJECT NO. WT17019

REFERENCE NOTES FOR FOUND MONUMENTS

FIELD CREW:

CITY OF STOCKTON, COUNTY OF SAN JOAQUIN

R. SNOW & A. MAWLAAE

LEGEND:

- ◆ FOUND MAG NAIL AND WASHER STAMPED "LS 6953", PER CR-21-229
- SET 1-1/4" BRASS DISC AS REFERENCE POINT, STAMPED "SURVEY POINT", IN TOP OF CURB
- SNF SEARCH NOTHING FOUND
- () RECORD DISTANCE PER CR-21-229
- BOW BACK OF WALK
- EP EDGE OF PAVEMENT
- CR CORNER RECORD, SAN JOAQUIN COUNTY SURVEYOR'S RECORDS
- M MAPS & PLATS, SAN JOAQUIN COUNTY RECORDS

#125, #126 & #127 - SET 1-1/4" BRASS DISC AS REFERENCE POINT, STAMPED "SURVEY POINT", IN TOP OF CURB

#17, #18 & #19 - FOUND MAG NAIL AND WASHER STAMPED "LS 6953", PER CR-21-229

FROM - TO	HZ. ANGLE	HZ. DISTANCE
125-17	00°00'00"	80.60'
125-126	∠ R = 26°04'44"	40.24'
125-19	∠ R = 254°30'44"	49.22'
125-127	∠ R = 315°12'52"	68.44'
125-18	∠ R = 326°32'23"	41.89'

