


CORNER RECORD

Agency Index CR-22-271
 Document Number _____

City of _____ County of San Joaquin, California
 Brief Legal Description West 1/2 of Northeast 1/4 of Section 7, T.2N., R.8E., M.D.B.&M., S.J.C.R.

CORNER TYPE



- Government Corner Control
 Meander Property
 Rancho Other

Date of Survey August 9, 2022

COORDINATES (Optional)

N. _____ E. _____

Elevation _____

Units Metric U.S. Survey Foot

Horizontal Datum _____

Zone _____ Epoch Date _____

Vertical Datum _____

Complies with Public Resources Code §§8801-8819

Complies with Public Resources Code §§8890-8902

T.2N., R.8E., M.D.B.&M.

PLS Act Ref.: 8765(d) 8771 8773 Other:

Corner/Monument: Left as found Established Rebuilt Pre-Construction
 Found and tagged Reestablished Referenced Post-Construction

Narrative of corner identified and monument as found, set, reset, replaced, or removed:

See sheet #2 for description(s):

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with
 the Professional Land Surveyors' Act on November 2, 2022
 Signed [Signature] (P.L.S.) or R.C.E. No. 7269



COUNTY SURVEYOR'S STATEMENT

This Corner Record was received November 2, 2022
 and examined and filed November 8, 2022
 Signed [Signature] P.L.S. or R.C.E. No. 8657
 Title County Surveyor



County Surveyor's Comment

FD. S.J.CO. BOLT
& WASHER IN MON.
BOX. AT 1/4 SEC. COR.
(NO VISIBLE STAMP)(R1)

FD. S.J.CO. BOLT
& WASHER IN MON.
BOX. AT 1/4 SEC. COR.
(NO VISIBLE STAMP)(R1)

COMSTOCK ROAD

S89°51'19"E 2644.68'(M)(R1)

SEC. 6

SEC. 5

SEC. 7

SEC. 8

T.2N., R.8E.,
M.D.B&M.

1/4 SEC. LINE

R.S. 34-120

138.4 ACRES
WEST 1/2 OF NORTHEAST 1/4
OF SEC. 7

N00°27'51"E 2650.56'(M)(R1)

FD. 1" IRON PIPE
(R1) NO TAG

SFN

S89°56'25"E 1322.77'(M)(R1)

LEGEND

FD.	FOUND	MON.	MONUMENT
R.S.	RECORD OF SURVEY	COR.	CORNER
(M)	MEASURED	SEC.	SECTION
S.J.C.R.	SAN JOAQUIN COUNTY RECORDS		
SFN	SEARCHED FOUND NOTHING		
S.J.CO.	SAN JOAQUIN COUNTY		
○	SET 3/4" X 30" IRON ROD CAPPED "LS 7269" OR AS NOTED.		
●	FOUND MONUMENT AS NOTED		

REFERENCE

(R1) R.S. 34-120, S.J.C.R.