


# CORNER RECORD

Agency Index CR-23-235  
Document Number \_\_\_\_\_

City of Lathrop County of San Joaquin, California  
Brief Legal Description Benchmark H1041 (HS0518) in SE 1/4, SE 1/4, Section 08, T02S R06E, MDM.

### CORNER TYPE

### COORDINATES (Optional)



- Government Corner
- Meander
- Rancho
- Control
- Property
- Other

Date of Survey November 1, 2022

N. \_\_\_\_\_ E. \_\_\_\_\_  
 Elevation 27.25  
 Units  Metric  U.S. Survey Foot  
 Horizontal Datum \_\_\_\_\_  
 Zone \_\_\_\_\_ Epoch Date \_\_\_\_\_  
 Vertical Datum \_\_\_\_\_  
 Complies with Public Resources Code §§8801-8819  
 Complies with Public Resources Code §§8890-8902

- PLS Act Ref.:  8765(d)  8771  8773  Other:
- Corner/Monument:  Left as found  Established  Rebuilt  Pre-Construction  
 Found and tagged  Reestablished  Referenced  Post-Construction

Narrative of corner identified and monument as found, set, reset, replaced, or removed:  
 See sheet #2 for description(s):

Found H1041 (PID HS0518) benchmark (3 1/2" dia. brass disc) stamped "U.S. COAST & GEODETIC SURVEY" on the Northerly end of concrete abutment at the Northerly end of bridge 29-32L in Manthey Rd. and level with the road centerline. According to NGS guidance, level ties were made to three reference points for replacement upon upgrade construction.

### SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with  
 the Professional Land Surveyors' Act on November 7, 2022  
 Signed [Signature] P.L.S. or R.C.E. No. LS8074



### COUNTY SURVEYOR'S STATEMENT

This Corner Record was received September 20, 2023  
 and examined and filed October 5, 2023  
 Signed James E. Hart P.L.S. or R.C.E. No. 8657  
 Title County Surveyor



County Surveyor's Comment

ELEVATION TIES TO BM H1041

RP1 -1.30 3/4" REBAR

RP2 -6.81 3/4" REBAR

RP3 -1.61 3/4" REBAR

APN 21003009  
FARMWORLD LLC



Billboard

Joint Util Pole

RP2  
3/4" Rebar  
93'  
N 52° 00' 00" E

Dirt Road

Swing Gate  
and  
Wooden Bollards

MANTHEY RD.

RP3  
3/4" Rebar  
122'  
N 36° 00' 00" W

Benchmark  
H1041

RP1  
3/4" Rebar  
85'  
S 72° 00' 00" E

Traffic Sign

APN 21003014  
RIVER ISLANDS  
EMPLOYMENT CTR

Concrete Bridge  
29-32L

INTERSTATE ROUTE 5

To Tracy

To Lathrop / Manteca