


CORNER RECORD

Agency Index CR-24-165
 Document Number _____

City of Lodi County of San Joaquin, California
 Brief Legal Description City of Lodi Benchmark 164 Reset



CORNER TYPE

Government Corner Control
 Meander Property
 Rancho Other

Date of Survey January 17, 2024

COORDINATES (Optional)

N. _____ E. _____
 Elevation _____
 Units Metric U.S. Survey Foot
 Horizontal Datum _____
 Zone _____ Epoch Date _____
 Vertical Datum NAVD88
 Complies with Public Resources Code §§8801-8819
 Complies with Public Resources Code §§8890-8902

PLS Act Ref.: 8765(d) 8771 8773 Other:
 Corner/Monument: Left as found Established Rebuilt Pre-Construction
 Found and tagged Reestablished Referenced Post-Construction

Narrative of corner identified and monument as found, set, reset, replaced, or removed:
 See sheet #2 for description(s):
 City of Lodi Benchmark 164 destroyed in construction. Ties shown on pre-construction corner record CR 20-15 were destroyed. Set 2-1/4" CALIF DEPT OF TRANSPORTATION Brass Disc Stamped "COL BM 164 RESET" in top of curb at back of walk. Established elevation on new mark is the result of adjusted differential level runs holding elevations on BM 1040 & BM 1212 per City of Lodi Benchmarks book revision date 02/15/18. Further information available on Survey Request No. 1910-0101 at Caltrans District 10 Surveys Office.

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act on March 21, 2024.
 Signed [Signature] P.L.S. or R.C.E. No. 9531



COUNTY SURVEYOR'S STATEMENT

This Corner Record was received March 21, 2024 and examined and filed April 1, 2024.
 Signed James E Hart P.L.S. or R.C.E. No. 8657
 Title County Surveyor



County Surveyor's Comment

CHEROKEE LN

● FOUND CITY OF LODI
BENCHMARK 1040
EL = 55.366'

SEE DETAIL

ROUTE 99

● SET 2-1/4" CALIF DEPT OF
TRANSPORTATION BRASS DISC
STAMPED "COL BM 164 RESET"
EL = 59.656'

BECKMAN RD

VICTOR RD

LOCKEFORD ST

VICTOR RD
BRIDGE OVER
ROUTE 99

BRIDGE RAIL &
SAFETY FENCE

APPROACH
SLAB

BM 164 RESET
CURB AT BACK
OF WALK

1.61'
SIDEWALK

VICTOR RD

PARK & RIDE

AC DIKE

DETAIL



NOT TO SCALE

CLUFF AVE

● FOUND CITY OF LODI
BENCHMARK 1212
EL = 56.553'