CORNER RECORD Agency Index Document Number SAN JOAQUIN , California STOCKTON County of _ City of _____ A PORTION OF SECTION 9, C.M. WEBER GRANT, BLOCKS 79, 95, 110, AND 111 Brief Legal Description _____ OF SOUTH OF MORMON CHANNEL, CITY OF STOCKTON, S.J.C.R. **COORDINATES (Optional) CORNER TYPE** ☐ Government Corner Control Elevation. U.S. Survey Foot □ Property Units ☐ Metric ☐ Meander Rancho Other Horizontal Datum _____ Epoch Date Date of Survey 02-07-2025 Vertical Datum Complies with Public Resources Code §§8801-8819 Complies with Public Resources Code §§8890-8902 Other: 8773 **8771** PLS Act Ref.: 8765(d) Established Rebuilt □ Pre-Construction Left as found Corner/ Monument: ☐ Post-Construction Referenced Found and tagged Reestablished Narrative of corner identified and monument as found, set, reset, replaced, or removed: See sheet #2 for description(s): LOCATED EXISTING CHISELED "X" OFFSET MONUMENTS FLUSH IN CONCRETE SIDEWALK, AT VARIOUS LOCATIONS SURVEYOR'S STATEMENT This Corner Record was prepared by me or under my direction in conformance with the Professional Land Surveyor's Act on COUNTY SURVEYOR'S STATEMENT This Corner Record was received March 13, 2025 No. 8657

County Surveyor's Comment

DATUM STATEMENT:

COORDINATES SHOWN HEREON ARE GRID AND ARE BASED ON CITY OF STOCKTON MONUMENTS 1S-10 AND 5S-21 CALIFORNIA COORDINATE SYSTEM (CCS83), ZONE III, 1983 NAD, AND SHOWN ON RECORD OF SURVEYS BOOK 33 OF SURVEYS, PAGE 20. THE PROJECT SPECIFIC SCALE FACTOR IS 0.9999389679370.

LEGEND:

- X INDICATES FOUND CHISELED "X" FLUSH IN CONCRETE SIDEWALK AS OFFSET MONUMENTS.
- INDICATES A PORTION OF SECTION 9, C.M. WEBER GRANT, BLOCKS 79, 95, 110 AND 111 OF SOUTH OF MORMON CHANNEL, CITY OF STOCKTON, S.J.C.R.


RS RECORD OF SURVEY, S.J.C.R.

S.J.C.R. SAN JOAQUIN COUNTY RECORDS

GRID COORDINATES (U.S. SURVEY FEET)		
Point	Northing	Easting
100	2165236.2508'	6333080.5303'
102	2165391.3461	6333046.4760'
103	2165594.2140'	6333004.5696'
104	2165657.2975'	6333311.6423'
105	2165721.3365'	6333371.2427'

S

LINCOLN




STATEMENT OF PURPOSE:

THE PURPOSE OF THIS SURVEY IS TO IDENTIFY AND RECORD THE LOCATION OF EXISTING MONUMENTS PRIOR TO THE CONSTRUCTION OF PG&E FACILITIES AROUND THE MONUMENTS. THE PURPOSE OF THIS SURVEY IS NOT TO MAKE PROPERTY LINE DETERMINATIONS. LOT LINES SHOWN HEREON ARE FOR GENERAL LOCATION AND INFORMATIONAL PURPOSES ONLY.

NOTE:

FIELD EFFORT INCLUDED A SEARCH FOR EXISTING CUT CROSSES AND CENTERLINE MONUMENTS AT THEIR TYPICAL LOCATION, ONLY THOSE FOUND ARE SHOWN.



110