

# CORNER RECORD

Agency Index CR-26-052  
Document Number \_\_\_\_\_

City of MANTECA

County of SAN JOAQUIN, California

Brief Legal Description INTERSECTION OF SILVERADO DRIVE AND CROM STREET



T.1S., R.7E.

### CORNER TYPE

- Government Corner
- Meander
- Rancho
- Control
- Property
- Other

Date of Survey 9/11/2025

### COORDINATES (Optional)

N. \_\_\_\_\_ E. \_\_\_\_\_  
 Elevation \_\_\_\_\_  
 Units  Metric  U.S. Survey Foot  
 Horizontal Datum \_\_\_\_\_  
 Zone \_\_\_\_\_ Epoch Date \_\_\_\_\_  
 Vertical Datum \_\_\_\_\_

- Complies with Public Resources Code §§8801-8819
- Complies with Public Resources Code §§8890-8902

PLS Act Ref:  8765(d)  8771  8773  Other:

Corner/Monument:  Left as found  Established  Rebuilt  Pre-Construction  
 Found and tagged  Reestablished  Referenced  Post-Construction

Narrative of corner identified and monument as found, set, reset, replaced, or removed:  
 See sheet #2 for description (s):

FOUND ONE (1) 2" BRASS DISK STAMPED "CITY OF MANTECA BENCHMARK #34"; SET FOUR (4) CONCRETE NAILS WITH BRASS TAG "LS 9857" AS WITNESS CORNERS, ALL AS SHOWN ON SHEET 2.

### SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act on JANUARY 5, 2026

Signed Tanya Cissell P.L.S. or R.C.E. No. 9857



### COUNTY SURVEYOR'S STATEMENT

This Corner Record was received January 5, 2026

and examined and filed January 9, 2026

Signed James E. Hart P.L.S. or R.C.E. No. 8657

Title County Surveyor



County Surveyor's Comment \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**LEGEND:**

- ⊗ SET CONCRETE NAIL WITH BRASS TAG "LS 9857".
- FOUND MONUMENT AS NOTED.
- M&P- MAPS AND PLATS
- S.J.C.R. SAN JOAQUIN COUNTY RECORDS
- (M) MEASURED DISTANCE. ALL DISTANCES ARE MEASURED UNLESS NOTED OTHERWISE.

**NOTE:**

THIS CORNER RECORD DOES NOT VERIFY THESE MONUMENTS TO BE IN THE CORRECT POSITION.

∠ AND DISTANCE TABLE		
BS-@-FS	∠	FS DISTANCE
B-A-B	00°00'00"	252.81'(M)
B-A-C	00°02'13"	141.57'(M)
B-A-D	38°07'28"	135.19'(M)
B-A-E	189°38'46"	144.66'(M)

ELEVATION TABLE	
MONUMENT	ELEVATION
"E"	100.000(ASSUMED)
"A"	99.943(M)
"D"	99.801(M)



SCALE: 1" = 50'

FOUND 2" BRASS DISK IN CURB STAMPED  
"CITY OF MANTECA BENCHMARK #34"

**CROM STREET**

**SILVERADO DRIVE**

**MURIETTA WAY**

27-M&P-65

"B" ⊗

"C" ⊗

"D" ⊗

"A" ⊗

"E" ●