


CORNER RECORD

Agency Index

CR-26-282

Document Number

City of STOCKTON County of SAN JOAQUIN, CaliforniaBrief Legal Description TRACT NO. 956 COLONIAL WEST, UNIT NO. 3, M&P 19-74, SAN JOAQUIN COUNTY RECORDSTRACT NO. 972 COLONIAL WEST, UNIT NO. 7, M&P 19-82, SAN JOAQUIN COUNTY RECORDS**CORNER TYPE****COORDINATES (Optional)**

- ☐ Government Corner ☐ Control
☐ Meander ☐ Property
☐ Rancho ☒ Other

Date of Survey 7/13/2026

N. _____ E. _____

Elevation. _____

Units ☐ Metric ☐ U.S. Survey Foot

Horizontal Datum _____

Zone _____ Epoch Date _____

Vertical Datum _____

☐ Complies with Public Resources Code §§8801-8819☐ Complies with Public Resources Code §§8890-8902

SECTION 17, TOWNSHIP 2 NORTH, RANGE 6 EAST, M.D.B. & M.

PLS Act Ref.: ☐ 8765(d) ☒ 8771 ☐ 8773 ☐ Other:Corner/ ☒ Left as found ☐ Established ☐ Rebuilt ☒ Pre-ConstructionMonument: ☐ Found and tagged ☐ Reestablished ☐ Referenced ☐ Post-Construction

Narrative of corner identified and monument as found, set, reset, replaced, or removed:

☒ See sheet #2 for description(s):FOUND EXISTING MONUMENTS PER M&P 19-74 AND M&P 19-82,
S.J.C.R. ALONG ARGUELLO DRIVE AS DESCRIBED ON SHEET #2

MONUMENTS WERE REFERENCED PRIOR TO CONSTRUCTION OF PG&E FACILITIES

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with

the Professional Land Surveyor's Act on AUGUST 7, 2026Signed Randell Scott West P.L.S. or R.C.E. No. 8663**COUNTY SURVEYOR'S STATEMENT**This Corner Record was received August 10, 2026and examined and filed August 24, 2026Signed Robert L. Borsdorf III P.L.S. or R.C.E. No. 9728Title County Surveyor

County Surveyor's Comment



STATEMENT OF PURPOSE:

THE PURPOSE OF THIS SURVEY IS TO IDENTIFY AND RECORD THE LOCATION OF EXISTING MONUMENTS PRIOR TO THE CONSTRUCTION OF PG&E FACILITIES AROUND THE MONUMENTS. THE PURPOSE OF THIS SURVEY IS NOT TO MAKE PROPERTY LINE DETERMINATIONS. LOT LINES SHOWN HEREON ARE FOR GENERAL LOCATION AND INFORMATIONAL PURPOSES ONLY.

DATUM STATEMENT:

COORDINATES SHOWN HEREON ARE GRID AND ARE BASED ON CITY OF STOCKTON MONUMENTS 4N-12 AND 4N-17 CALIFORNIA COORDINATE SYSTEM (CCS83), ZONE III, 1983 NAD, AND SHOWN ON RECORD OF SURVEYS BOOK 33 OF SURVEYS, PAGE 20. THE PROJECT SPECIFIC SCALE FACTOR IS 0.9999404167723.

NOTE:

FIELD EFFORT INCLUDED A SEARCH FOR EXISTING MONUMENTS AT THEIR TYPICAL LOCATION, ONLY THOSE FOUND ARE SHOWN.

LEGEND:

- ⊙ INDICATES FOUND 3/4" IRON PIPE NO TAG IN CAST IRON MONUMENT BOX
- ⊗ INDICATES FOUND 3/4" IRON PIPE NO TAG IN DIRT BENT 45 DEGREES TO THE EAST
- INDICATES RIGHT OF WAY

M&P MAPS & PLATS

S.J.C.R. SAN JOAQUIN COUNTY RECORDS

