COUNTY OF SAN JOAQUIN – DEPARTMENT OF PUBLIC WORKS
DESIGN ENGINEERING SERVICES FOR THE COUNTRY CLUB BOULEVARD COMPLETE STREETS PROJECT REQUEST FOR PROPOSALS
SJCDPW-RFP-26-09

QUESTIONS & ANSWERS
11/13/26

QUESTION #1: Is the Disclosure of Lobbying Activities required for subconsultants?

ANSWER #1: Yes.

QUESTION #2: Is an 11x17 sheet permitted for the schedule or any exhibits? If so, would those count as 1 page or 2 pages?

ANSWER #2: Each page of the proposal must be numbered, and the total number of pages may not exceed fifty (50) pages, double-sided, standard pages (8 ½ by 11")

QUESTION #3: If a firm has comments or exceptions to the sample agreement, should those be included in the proposal? If so, would that be included in the fifty (50) page limit, or may proposers include those in an appendix?

ANSWER #3: The Agreement will remain as currently stated for this solicitation. Any comments or exceptions are included in the 50-page limit.

QUESTION #4: Does the County's stormwater permit require post construction treatment, such as bioswales, for replaced impervious area on this project?

ANSWER #4: The County does not anticipate post construction treatment in these locations as areas currently without sidewalks are already paved.

QUESTION #5**:** Should the design assume full pavement reconstruction, grind and overlay, or slurry seal where the exhibits show work? Will the County provide a geotechnical report, or should the consultant include one?

ANSWER #5: No, the pavement will not be fully reconstructed.

QUESTION #6: Should utility potholing be included in the consultant's scope?

ANSWER #6: The consultant should include potholing as necessary for their design and new facilities which may require excavation or digging underground.

COUNTY OF SAN JOAQUIN – DEPARTMENT OF PUBLIC WORKS
DESIGN ENGINEERING SERVICES FOR THE COUNTRY CLUB BOULEVARD COMPLETE STREETS PROJECT REQUEST FOR PROPOSALS
SJCDPW-RFP-26-09

QUESTIONS & ANSWERS
11/13/26

QUESTION #7: Is design of new inlets and storm drain piping part of the scope?

ANSWER #7: The area already has storm drainage. While new sidewalk may require adjustment or relocation of some facilities, we do not anticipate having to do a full storm drainage system design.

QUESTION #8: Is restoration of damaged existing sidewalk, to bring the path of travel up to current ADA standards, included beyond the curb extensions?

ANSWER #8: Damage to the existing sidewalk has not been evaluated. There may be some limited areas of sidewalk repair but full evaluation and replacement is not part of the scope of this project.

QUESTION #9: For Alternative 2, was a lighting analysis performed? Are street lighting design, photometrics, and PG&E service coordination in scope?

ANSWER #9: The scope of work provided was for alternative 1 not alternative 2.

QUESTION #10: Is the project federally funded, so that Caltrans Local Assistance procedures apply?

ANSWER #10: No.

QUESTION #11: Does the County require Geometric Approval Plans, and at which PS&E milestones should submittals be made?

ANSWER #11: The roadway is not being redesigned. Any design features of the sidewalk will be submitted with the 35%.

QUESTION #12: Can we alter the task effort worksheet to include additional tasks that may need to be completed?

ANSWER #12: Yes, the consultant should provide the scope of work as they deem necessary to complete the design.